

**EARTHWORK SCHEDULE**

FROM STATION	TO STATION	{SUITABLE} EARTH EXCAVATION (CU YD)	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (CU YD)	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR 15% SHRINKAGE (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)	TOPSOIL EXCAVATION AND PLACEMENT (CU YD)	TOPSOIL PLACED (CU YD)	TOPSOIL BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)
PAUL DOUGLAS TRAIL (Continued)									
265+00	265+50	0		0	102	-102	19	14	5
265+50	266+00	0		0	112	-112	20	15	5
266+00	266+50	0		0	119	-119	20	15	5
266+50	267+00	0		0	126	-126	20	15	5
267+00	267+50	0		0	149	-149	21	17	4
267+50	268+00	0		0	199	-199	25	21	4
268+00	268+50	0		0	218	-218	24	22	2
268+50	269+00	0		0	152	-152	21	16	5
269+00	270+00	7		6	100	-94	27	17	10
270+00	271+00	8		7	16	-9	22	10	12
271+00	272+00	0		0	91	-91	32	22	10
272+00	272+70	0		0	127	-127	25	15	10
272+70	273+00	1		1	33	-32	8	3	5
273+00	274+00	3		3	13	-10	20	10	10
274+00	275+00	1		1	24	-23	23	13	10
275+00	276+00	0		0	26	-26	23	13	10
276+00	277+00	3		3	16	-13	23	12	12
277+00	278+00	8		7	6	1	20	9	11
278+00	279+00	10		9	2	7	19	7	12
279+00	280+00	8		7	8	-1	22	10	12
280+00	281+00	6		5	22	-17	26	15	11
281+00	282+00	17		14	30	-16	30	20	10
282+00	283+00	195		166	15	151	37	29	8
283+00	284+00	277		235	0	235	39	31	8
284+00	285+00	106		90	0	90	26	16	10
285+00	286+00	12		10	17	-7	21	9	12
286+00	287+00	1		1	20	-19	21	10	11
287+00	288+00	10		9	3	6	20	8	12
288+00	289+00	35		30	0	30	21	9	12
289+00	290+00	36		31	0	31	21	9	12
290+00	291+00	10		9	12	-4	20	9	11
291+00	292+00	33		28	12	16	22	12	11
292+00	293+00	36		31	1	30	20	10	10
293+00	294+00	8		7	2	5	18	7	11
294+00	295+00	5		4	37	-33	23	12	12
295+00	296+00	3		3	38	-35	22	12	11
296+00	297+00	8		7	2	5	19	7	12
297+00	298+00	5		4	39	-35	23	12	12
298+00	299+00	0		0	108	-108	29	20	9
299+00	300+00	57		48	70	-22	31	18	13
300+00	301+00	96		82	0	82	26	14	12
301+00	302+00	39		33	92	-59	30	17	13
302+00	303+00	18		15	92	-77	30	18	12
303+00	304+00	29		25	1	24	22	10	12
304+00	305+00	12		10	8	2	21	10	11
305+00	306+00	19		16	7	9	21	10	11
306+00	307+00	20		17	3	14	20	9	11
307+00	308+00	16		14	4	10	21	10	11
308+00	309+00	17	8	14	3	11	21	10	11
309+00	310+00	3		3	12	-9	21	9	12
310+00	311+00	5		4	13	-9	22	10	12
311+00	312+00	17		14	4	10	22	10	12
312+00	313+00	13		11	8	3	21	10	11
313+00	314+00	10		9	8	1	20	9	11
314+00	315+00	11		9	9	0	21	10	11
315+00	316+00	1		1	31	-30	23	12	12
316+00	317+00	1		1	27	-26	23	12	12
317+00	318+00	1		1	23	-22	22	12	11
318+00	319+00	0		0	138	-138	31	22	9
319+00	320+00	2		2	122	-120	29	20	9
320+00	321+00	2		2	9	-7	20	9	11
321+00	322+00	0		0	54	-54	25	15	10
322+00	323+00	0	18	0	57	-57	24	15	9
323+00	324+00	10		9	9	-1	18	8	10
324+00	325+00	10		9	23	-15	21	10	11
325+00	326+00	0		0	104	-104	29	20	9

FROM STATION	TO STATION	{SUITABLE} EARTH EXCAVATION (CU YD)	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (CU YD)	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR 15% SHRINKAGE (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)	TOPSOIL EXCAVATION AND PLACEMENT (CU YD)	TOPSOIL PLACED (CU YD)	TOPSOIL BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)
PAUL DOUGLAS TRAIL (Continued)									
326+00	327+00	14		12	80	-68	26	17	9
327+00	327+68	17		14	0	14	13	6	7
327+68	328+00	8		7	0	7	6	2	4
328+00	329+00	21		18	0	18	19	7	12
329+00	330+00	9		8	2	6	18	7	11
330+00	331+00	11		9	2	7	19	7	12
331+00	332+00	15		13	0	13	18	7	11
332+00	333+00	15		13	0	13	19	7	12
333+00	334+00	22		19	0	19	19	7	12
334+00	335+00	20		17	0	17	18	7	11
335+00	336+00	8		7	21	-14	20	9	11
336+00	337+00	0		0	64	-64	24	13	11
337+00	339+00	1		1	173	-172	57	37	20
339+00	340+00	4		3	65	-62	26	15	11
340+00	341+00	3		3	104	-101	29	17	12
341+00	342+00	0		0	181	-181	34	25	9
342+00	343+00	0		0	118	-118	30	20	10
343+00	344+00	6		5	21	-16	22	12	11
344+00	345+00	13		11	11	0	23	12	12
345+00	346+00	11		9	10	-1	22	12	11
346+00	346+09	1		1	0	1	1	1	0
346+09	347+00	9		8	1	7	17	7	10
347+00	348+00	11		9	0	9	17	7	10
348+00	348+61	4		3	0	3	6	2	4
<b>TOTAL</b>		<b>5711</b>	<b>189</b>	<b>4854</b>	<b>9853</b>	<b>-4999</b>	<b>6049</b>	<b>3347</b>	<b>2702</b>

**EARTHWORK SUMMARY**

LOCATION	{SUITABLE} EARTH EXCAVATION (CU YD)	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (CU YD)	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR 15% SHRINKAGE (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)	TOPSOIL EXCAVATION AND PLACEMENT (CU YD)	TOPSOIL PLACED (CU YD)	TOPSOIL BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)
PAY ITEM	20200100	20201200				21101505		
CRABTREE	862	100	733	676	57	1143	584	559
PARKING LOT	444	0	377	0	377	296	50	246
STOVER BUFFER RESTORATION	96	0	82	0	82	96	48	48
PAUL DOUGLAS	5711	189	4854	9853	-4999	6049	3347	2702
GRAVEL LOT RESTORATION	196	0	167	0	167	196	98	98
* ANTICIPATED COMPENSATORY STORAGE	-	150	-	-	-	-	-	-
<b>GRAND TOTAL</b>	<b>7309</b>	<b>439</b>	<b>6213</b>	<b>10,529</b>	<b>-4316</b>	<b>7780</b>	<b>4127</b>	<b>3653</b>

\* LOCATIONS TO BE DETERMINED IN THE FIELD

ILLINOIS DEPARTMENT OF TRANSPORTATION  
DISTRICT NO. 1 SCHAUMBURG

**EARTHWORK SCHEDULE**

SCALE NONE  
DATE 3/29/06  
DRAWN BY RTA  
CHECKED BY SMH