

FAU RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1389	99-00062-00-PV	DUPAGE	199	3
CONTRACT NO. 83873				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				

**SUMMARY OF QUANTITIES**

LINE NO.	CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	IDOT FUND CODE			
					1000-1A	Y003	Y007	NON-PARTICIPATING (CITY) Y060
1	20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	798		798		
2	20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	531		531		
3	20101000	TEMPORARY FENCE	FOOT	1200		1200		
4	20101200	TREE ROOT PRUNING	EACH	34		34		
5	20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	3		3		
6	20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	31		31		
7	20200100	EARTH EXCAVATION	CU YD	37746	37746			
8	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	14038	13651		387	
9	20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	387			387	
10	20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	8100	8100			
11	20800250	TRENCH BACKFILL, SPECIAL	CU YD	13227			10419	2808
12	20900110	POROUS GRANULAR BACKFILL	CU YD	58			58	
13	21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	36627	36627			
14	21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	6271		6271		
15	21101615	TOPSOIL FURNISH AND PLACE 4"	SQ YD	39150		39150		
16	21101625	TOPSOIL FURNISH AND PLACE 6"	SQ YD	3810		3810		
17	21300010	EXPLORATION TRENCH, SPECIAL	FOOT	60	60			
18	* 25000110	SEEDING, CLASS 1A	ACRE	8.44		8.44		
19	* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1048		1048		
20	* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	1048		1048		
21	* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	1048		1048		
22	* 25002014	SEEDING, CLASS 4A (MODIFIED)	ACRE	0.27		0.27		
23	* 25002024	SEEDING, CLASS 4B (MODIFIED)	ACRE	2.94		2.94		
24	* 25100105	MULCH, METHOD 1	ACRE	3.21		3.21		
25	* 25100115	MULCH, METHOD 2	ACRE	7.65		7.65		
26	* 25100630	EROSION CONTROL BLANKET	SQ YD	27283		27283		
27	* 28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	175		175		
28	28000300	TEMPORARY DITCH CHECKS	EACH	58		58		
29	28000400	PERIMETER EROSION BARRIER	FOOT	26429		26429		
30	28000500	INLET AND PIPE PROTECTION	EACH	122		122		
31	28000510	INLET FILTERS	EACH	112		112		
32	28100105	STONE RIPRAP, CLASS A3	SQ YD	20		20		
33	28100107	STONE RIPRAP, CLASS A4	SQ YD	69			69	
34	28200200	FILTER FABRIC	SQ YD	89		89		
35	35100300	AGGREGATE BASE COURSE, TYPE A 4"	SQ YD	249	249			
36	35100500	AGGREGATE BASE COURSE, TYPE A 6"	SQ YD	10315	10315			
37	35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SQ YD	1238	1238			
38	35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	2953	2953			
39	40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	1100	1100			
40	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	27952	27952			
41	40600300	AGGREGATE (PRIME COAT)	TON	33	33			
42	40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	230	230			
43	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	234	234			
44	40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	2304	2304			

\* SPECIALTY ITEM

LINE NO.	CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	IDOT FUND CODE			
					1000-1A	Y003	Y007	NON-PARTICIPATING (CITY) Y060
45	40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	358	358			
46	40701881	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 10"	SQ YD	13471	13471			
47	40701941	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 13"	SQ YD	32563	32563			
48	40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	92	92			
49	42001300	PROTECTIVE COAT	SQ YD	11249	11249			
50	42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	98	98			
51	42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	2025	2025			
52	42400430	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH, SPECIAL	SQ FT	8239	8239			
53	42400800	DETECTABLE WARNINGS	SQ FT	562	562			
54	44000100	PAVEMENT REMOVAL	SQ YD	30771	30771			
55	44000180	HOT-MIX ASPHALT SURFACE REMOVAL, 2 3/4"	SQ YD	4103	4103			
56	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	7929	7929			
57	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1665	1665			
58	44000800	SIDEWALK REMOVAL	SQ FT	14182	14182			
59	44201785	CLASS D PATCHES, TYPE I, 12 INCH	SQ YD	70	70			
60	44201789	CLASS D PATCHES, TYPE II, 12 INCH	SQ YD	80	80			
61	44201794	CLASS D PATCHES, TYPE III, 12 INCH	SQ YD	90	90			
62	44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SQ YD	65	65			
63	48100500	AGGREGATE SHOULDERS, TYPE A 6"	SQ YD	997	997			
64	50105220	PIPE CULVERT REMOVAL	FOOT	1207			1207	
65	51500100	NAME PLATES	EACH	1			1	
66	54001000	BOX CULVERT END SECTIONS	EACH	2			2	
67	54020805	PRECAST CONCRETE BOX CULVERT 8'X5' (M273)	FOOT	192			192	
68	54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	1			1	
69	54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	3			3	
70	54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	1			1	
71	54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	2			2	
72	54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	2			2	
73	54217711	REINFORCED CONCRETE PIPE TEE, 42" PIPE WITH 24" RISER	EACH	1			1	
74	54247130	GRATING FOR CONCRETE FLARED END SECTION 24"	EACH	2			2	
75	54247170	GRATING FOR CONCRETE FLARED END SECTION 36"	EACH	2			2	
76	54248510	CONCRETE COLLAR	CU YD	1			1	
77	550A2320	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 12"	FOOT	808			808	
78	550A2330	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 15"	FOOT	174			174	
79	550A2340	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 18"	FOOT	363			363	
80	550A2360	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 24"	FOOT	47			47	
81	550A2400	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 36"	FOOT	236			236	
82	550A2520	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 12"	FOOT	1513			1513	
83	550A2530	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 15"	FOOT	819			819	
84	550A2540	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 18"	FOOT	989			989	
85	550A2560	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 24"	FOOT	2481			2481	

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SUMMARY OF QUANTITIES  
HAWTHORNE LANE**

SCALE: NONE  
DATE: 1/8/2007

DRAWN BY: PMW  
DESIGN BY: BLL  
CHECKED BY: JGS