

F.A.U. R/L	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1389	99-00062-00-PV	DUPAGE	199	5
CONTRACT NO. 83873				
ILLINOIS FED. AID PROJECT				

SUMMARY OF QUANTITIES

LINE NO.	CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	IDOT FUND CODE			
					1000-1A	Y003	Y007	NON-PARTICIPATING (CITY) Y060
172	78300100	PAVEMENT MARKING REMOVAL	SQ FT	1384	1384			
173	80400100	ELECTRIC SERVICE INSTALLATION	EACH	4	4			
174	81000700	CONDUIT IN TRENCH, 2 1/2" DIA. GALVANIZED STEEL	FOOT	610	610			
175	81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	9500	9500			
176	82500530	LIGHTING CONTROLLER CB-RCS-100 AMP-240 VOLT	EACH	4	4			
177	83006500	LIGHT POLE, ALUMINUM, 30 FT. M.H., 12 FT. MAST ARM	EACH	60	60			
178	83007600	LIGHT POLE, ALUMINUM, 35 FT. M.H., 15 FT. MAST ARM	EACH	21	21			
179	83600200	LIGHT POLE FOUNDATION, CONCRETE, 24" DIAMETER	FOOT	729	729			
180	83600215	LIGHT POLE FOUNDATION, CONCRETE, 24" DIAMETER, OFFSET	FOOT	108	108			
181	83800105	BREAKAWAY DEVICE, TRANSFORMER BASE, 11.5 INCH BOLT CIRCLE	EACH	81	81			
182	84200700	LIGHTING FOUNDATION REMOVAL	EACH	7	7			
183	84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	6	6			
184	84500120	REMOVAL OF ELECTRIC SERVICE INSTALLATION	EACH	1	1			
185	84500130	REMOVAL OF LIGHTING CONTROLLER FOUNDATION	EACH	1	1			
186	A2000916	TREE, ACER PLATANOIDES EMERALD QUEEN, (EMERALD QUEEN NORWAY MAPLE), 2" CALIPER, BALLED AND BURLAPPED	EACH	5		5		
187	A2001116	TREE, ACER RUBRUM OCTOBER GLORY (OCTOBER GLORY RED MAPLE), 2" CALIPER, BALLED AND BURLAPPED	EACH	12		12		
188	A2002916	TREE, CELTIS OCCIDENTALIS (COMMON HACKBERRY), 2" CALIPER, BALLED AND BURLAPPED	EACH	10		10		
189	A2008516	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	26		26		
190	A2007116	TREE, QUERCUS RUBRA (RED OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	15		15		
191	A2008116	TREE, TILIA CORDATA GREENSPIRE (GREENSPIRE LITTLE LEAF LINDEN), 2" CALIPER, BALLED AND BURLAPPED	EACH	6		6		
192	B2004316	TREE, MALUS RADIANT (RADIANT CRABAPPLE), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	9		9		
193	B2005016	TREE, MALUS SNOWDRIFT (SNOWDRIFT CRAB APPLE), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	13		13		
194	B2005316	TREE, MALUS ZUMI CALOCARPA (REDBUD ZUMI CRABAPPLE), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	5		5		
195	B2005616	TREE, PYRUS CALLERYANA BRADFORD (BRAD FORD CALLERY PEAR), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	12		12		
196	C2C05815	SHRUB, RHUS AROMATICA GRO-LOW (GRO-LOW FRAGRANT SUMAC), 15" WIDTH, CONTAINER	EACH	94		94		
197	MX033634	SNOWPLOWABLE RAISED PAVEMENT MARKER	EACH	97	97			
198	X0321461	PILLAR REMOVAL	EACH	6	6			
199	X0321478	MAINTENANCE OF EXISTING LIGHTING SYSTEM, COMPLETE	L SUM	1	1			
200	X0321690	BRICK WALL REMOVAL	FOOT	67	67			
201	X0322089	STORM SEWERS, (WATER MAIN REQUIREMENTS) 36 INCH	FOOT	75			75	
202	X0322671	STABILIZED CONSTRUCTION ENTRANCE	SQ YD	200	200			
203	X0322936	REMOVE EXISTING FLARED END SECTION	EACH	21			21	
204	X0323381	STORM SEWERS, (WATER MAIN REQUIREMENTS) TYPE 1, 12"	FOOT	1130			1130	
205	X0323382	STORM SEWERS, (WATER MAIN REQUIREMENTS) TYPE 1, 15"	FOOT	67			67	
206	X0323863	STORM SEWERS, (WATER MAIN REQUIREMENTS) TYPE 2, 12"	FOOT	855			855	
207	X0323889	STORM SEWERS, (WATER MAIN REQUIREMENTS) TYPE 2, 18"	FOOT	178			178	
208	X0330200	SANITARY MANHOLES TO BE ADJUSTED	EACH	17			17	
209	X0350810	BOLLARD REMOVAL	EACH	14	14			
210	X8063401	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.12	FOOT	224	224			

LINE NO.	CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	IDOT FUND CODE			
					1000-1A	Y003	Y007	NON-PARTICIPATING (CITY) Y060
211	X8063600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.24	FOOT	324	324			
212	X6020095	MANHOLES, TYPE A, 4' DIAMETER, TYPE 1 FRAME, CLOSED LID, RESTRICTOR PLATE	EACH	1			1	
213	X8950077	REMOVE AND RELOCATE EXISTING LIGHTING CONTROLLER	EACH	1	1			
214	XX000610	RELOCATE EXISTING MAILBOX	EACH	21	21			
215	XX000876	LUMINAIRE, METAL HALIDE, HORIZONTAL MOUNT, 250 WATT	EACH	81	81			
216	XX001607	RETAINING WALL, SPECIAL	SQ FT	300			300	
217	XX003817	GRATING FOR CONCRETE FLARED END SECTION 12"	EACH	1			1	
218	XX004700	SANITARY SEWER REMOVAL AND REPLACEMENT 15"	FOOT	172				172
219	XX004810	VALVE VAULTS, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3				3
220	XX005758	TEMPORARY PAVEMENT	TON	1773	1773			
221	XX005920	SEEDING, WET PRAIRIE	ACRE	4.48		4.48		
222	XX006144	SEEDING, MESIC PRAIRIE	ACRE	0.15		0.15		
223	XX006634	DUCTILE IRON PIPE INSTALLED IN STEEL CASING, 16"	FOOT	100			50	50
224	XX006639	STEEL CASING PIPE IN OPEN CUT 30"	FOOT	100			50	50
225	XX006641	STORM SEWERS, (WATER MAIN REQUIREMENTS) TYPE 1, 36"	FOOT	47			47	
226	XX006643	STORM SEWERS, (WATER MAIN REQUIREMENTS) TYPE 2, 24"	FOOT	463			463	
227	Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	53600	53600			
228	Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1			
229	Z0019600	DUST CONTROL WATERING	UNIT	6	6			
230	Z0022800	FENCE REMOVAL	FOOT	1321	1321			
231	Z0030250	IMPACT ATTENUATOR, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	6	6			
232	Z0030350	IMPACT ATTENUATOR RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	4	4			
233	Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1			
234	Z0056900	SANITARY SEWER 8"	FOOT	100				100
235	Z0057200	SANITARY SEWER 15"	FOOT	475				475
236	Z0078600	TRAINEES	HOURL	1500	1500			
237	Z0077700	WOOD FENCE TO BE REMOVED AND RE-ERECTED	FOOT	65	65			
238	XX006833	LUMINAIRE, METAL HALIDE, VERTICAL MOUNT, 50 WATT	EACH	37	37			
239	XX006840	UNIT DUCT, 1 1/2" HDPE, WITH 4/C #6, 1/C #6 GND XLP TYPE USE, 600V	FOOT	11000	11000			
240	XX006834	ELECTRICAL CONNECTION TO EXISTING LIGHTING SYSTEM	EACH	7	7			
241	XX005559	SANITARY SEWER FOR SERVICES	FOOT	30				30
242	XX006835	WATER MAIN LINE STOP 24"	EACH	1				1
243	XX006836	TEMPORARY STORM SEWER 15"	FOOT	124			124	
244	XX006837	STORM SEWERS, (WATER MAIN REQUIREMENTS) TYPE 2, 36"	FOOT	224			224	
245	XX006838	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1, REINFORCED ELLIPTICAL CONCRETE PIPE, SPAN 53, RISE 34	FOOT	15			15	
246	XX006839	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2, REINFORCED ELLIPTICAL CONCRETE PIPE, SPAN 53, RISE 34	FOOT	31			31	

Δ Y080

• SPECIALTY ITEM

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION	
NAME	DATE	<p align="center">SUMMARY OF QUANTITIES HAWTHORNE LANE</p> <p>SCALE: NONE DATE: 1/8/2007</p> <p>DRAWN BY: PMM DESIGN BY: BLL CHECKED BY: JGS</p>	

N:\WestCh\04479\04479.TBL