

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1700	05-00045-02-PV	COOK/DUPAGE	103	8
SCHEDULE OF QUANTITIES				
FED. ROAD DIST. NO. 7		ILLINOIS	FED. AID PROJECT M-80035441	

PROPOSED LOCATION	DIMENSIONS	AREA (SQ FT)	TELESCOPING STEEL SIGN SUPPORT (FT)
11+40, RT	12"x18"	1.5	0
15+30, RT	12"x18"	1.5	13.5
15+85, LT	12"x18"	1.5	13.5
17+90, LT	12"x18"	1.5	13.5
21+50, RT	12"x18"	1.5	13.5
22+00, LT	12"x18"	1.5	13.5
23+45, LT	18" DIA.	1.8	13.5
23+60, LT	18" DIA.	1.8	13.5
25+00, RT	12"x18"	1.5	13.5
25+65, LT	12"x18"	1.5	13.5
29+40, RT	12"x18"	1.5	0
30+80, LT	12"x18"	1.5	13.5
31+60, LT	18" DIA.	1.8	13.5
31+60, RT	18" DIA.	1.8	13.5
31+80, LT	18" DIA.	1.8	13.5
33+35, RT	12"x18"	1.5	13.5
33+70, LT	36" DIA.	7.1	0
33+70, LT	12"x18"	1.5	16.5
37+50, RT	12"x18"	1.5	0
37+50, LT	12"x18"	1.5	13.5
39+25, LT	18" DIA.	1.8	13.5
39+50, LT	48"x9"	6	14
39+50, LT	18" DIA.	1.8	13.5
40+95, RT	12"x18"	1.5	13.5
41+15, LT	12"x18"	1.5	0
44+20, RT	12"x18"	1.5	0
44+85, LT	12"x18"	1.5	13.5
45+95, LT	18" DIA.	1.8	13.5
46+20, LT	18" DIA.	1.8	13.5
47+75, RT	12"x18"	1.5	13.5
48+40, LT	12"x18"	1.5	0
50+84, RT	12"x18"	1.5	0
51+35, LT	12"x18"	1.5	13.5
51+80, RT	36" DIA.	7.1	15
52+90, LT	18" DIA.	1.8	13.5
52+90, RT	48"x9"	6	14
53+15, LT	18" DIA.	1.8	13.5
53+85, RT	12"x18"	1.5	13.5
55+10, LT	12"x18"	1.5	0
58+00, RT	12"x18"	1.5	0
58+80, LT	12"x18"	1.5	13.5
59+75, LT	18" DIA.	1.8	13.5
59+95, LT	18" DIA.	1.8	13.5
61+05, LT	36" DIA.	7.1	15
61+60, RT	12"x18"	1.5	13.5
61+85, LT	12"x18"	1.5	0
61+85, LT	18"x24"	3	15.5
608+25, RT	36"x36"	9	16
611+75, LT	36"x36"	9	16

SEE TRAFFIC SIGNAL SHEETS FOR ADDITIONAL QUANTITIES

FROM	TO	LETTERS & SYMBOLS (SQFT)	LINE 4" (FT)	LINE 6" (FT)	LINE 12" (FT)	LINE 24" (FT)
LIVELY BOULEVARD						
7+87	DEVON	36.4	924	183	199	31
DEVON	ARTHUR	135.2	2103	438	225	42
ARTHUR	PRATT	130	2221	320	46	37
PRATT	MORSE	98.8	1589	299	51	36
MORSE	LUNT	124.8	1403	0	0	0
LUNT	GREENLEAF	98.8	1658	289	51	31
GREENLEAF	ESTES	98.8	1588	312	51	36
ESTES	TOUHY	98.8	1560	310	51	35
ARTHUR		0	254	277	0	61
PRATT		0	226	264	0	57
MORSE		0	282	272	0	59
LUNT		0	308	288	0	63
GREENLEAF		0	232	253	0	56
ESTES		0	248	299	0	64
TOUHY		0	328	278	0	61

PROPOSED LOCATION	AREA (SQ FT)
STA. 7+87 TO 8+68, LT	487
STA. 10+70 TO 11+31, RT	370
STA. 11+44 TO 13+35, LT	1,118
STA. 17+40 TO 17+87, RT	274
STA. 27+06 TO 27+97, RT	282

PROPOSED LOCATION	LENGTH (FT)
STA. 14+66.5, LT	50
STA. 14+66.5, RT	50
STA. 22+71, LT	50
STA. 23+42.7, RT	50
STA. 30+98, LT	50
STA. 31+34.4, RT	50
STA. 35+13.8, RT	50
STA. 38+10.3, LT	50
STA. 38+10.3, RT	50
STA. 41+95.6, LT	50
STA. 42+05.5, RT	50
STA. 42+90, LT	50
STA. 42+75.0, RT	50
STA. 46+57, RT	50
STA. 46+72, LT	50
STA. 50+06.1, LT	50
STA. 53+61, RT	50
STA. 53+77, LT	50
STA. 56+93.7, LT	50
STA. 60+44, RT	50
STA. 60+61, LT	50

ITEM	UNIT	STAGE 1A	STAGE 1B	STAGE 2A	STAGE 2B	TOTALS
EARTH EXCAVATION	C.Y.	4946	4638	3025	3009	15618
EARTH EXCAVATION ADJUSTED FOR SHRINKAGE	C.Y.	4204	3942	2571	2558	13275
EMBANKMENT REQUIRED	C.Y.	428	472	204	223	1327
EARTHWORK BALANCE						
WASTE (+) OR SHORTAGE (-)	C.Y.	+3776	+3470	+2367	+2335	+11948

SHRINKAGE CALCULATED USING 15% SHRINKAGE FACTOR

A PAY ITEM FOR "FURNISHED EXCAVATION" HAS BEEN INCLUDED ON THE ASSUMPTION THAT, DUE TO LIMITED WORKING SPACE, ALL EMBANKMENT MAY HAVE TO BE BROUGHT IN FROM OUTSIDE THE PROJECT LIMITS.

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCHEDULE OF QUANTITIES

DRAWN BY DJK
CHECKED BY JRV

DATE 10/18/06