

F.A.U. ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1342	06-00029-00-RS	KANE	14	3
STA.	TO STA.	ILLINOIS	FED AID PROJECT	
C-91-089-07			M-8003 (729)	

CONTRACT NO.: 83892

SUMMARY OF QUANTITIES

CODE NO.	PAY ITEM	UNIT	1000
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	4,688
40600300	AGGREGATE (PRIME COAT)	TON	94
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	1,077
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D" N70	TON	2,090
42400100	PORTLAND CEMENT CONCRETE SIDEWALK, 4 INCH	SQ FT	1,827
42400800	DETECTABLE WARNINGS	SQ FT	350
44000158	HOT-MIX ASPHALT SURFACE REMOVAL 2 1/4"	SQ YD	23,440
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	775
44004700	SIDEWALK REMOVAL (SPECIAL)	SQ FT	2,160
60250200	CATCH BASINS TO BE ADJUSTED	EACH	7
60255500	MANHOLES TO BE ADJUSTED	EACH	24
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	10
60266600	VALVE BOXES TO BE ADJUSTED	EACH	6
67100100	MOBILIZATION	LSUM	1
70102620	TRAFFIC CONTROL AND PROTECTION STANDARD 701501	LSUM	1
70300100	SHORT-TERM PAVEMENT MARKINGS	FOOT	2,638
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	880
** 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	88
** 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	11,223
** 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	221
** 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1,584
** 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	287
X0321556	SANITARY MANHOLE TO BE ADJUSTED	EACH	13
X0321558	SANITARY MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	4
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51.4
XX002895	SANITARY MANHOLES TO BE RECONSTRUCTED WITH NEW FRAME & LID	EACH	1

** - INDICATES SPECIALITY ITEM

I:\SELECT\051124\LAPP-DWGS\from Craylake\051124-QUANT.dwg - SH3
 Plotfile: 11-30-06 @ 2.37am By: 362/jmp
 Copyright © 2006, By Baxter & Woodman, Inc.
 State of Illinois - Professional Design Firm
 License No. - 184-001121 - Expires 4-30-07

CONSULTANTS	REV. NO.	DATE	DESCRIPTION
	1	11-01-06	PER I.D.O.T. REVIEW
	2	11-22-06	PER I.D.O.T. REVIEW

* - REFER TO EQUIPMENT MANUFACTURER'S SHOP DRAWINGS

Baxter & Woodman
 Crystal Lake, Illinois 815.450.1200
 Burlington, Wisconsin 262.762.7894
 Mokena, Illinois 708.478.2090
 DeKalb, Illinois 815.287.3111
 Grayslake, Illinois 847.223.5088
 Rockford, Illinois 815.486.1551
 Plainfield, Illinois 815.609.7425
 Consulting Engineers

VILLAGE OF SOUTH ELGIN, ILLINOIS
FAU 1342 SPRING STREET
STP (LAPP) IMPROVEMENTS

DESIGNED BY	JRR	SCALE	NONE
DRAWN BY	UKB	PROJECT NO.	051124
CHECKED BY	MWP	SHEET NO.	
DATE	8/18/06		

SUMMARY OF QUANTITIES