



FA RITE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
178	03-00287-00-BR	LEE	18	17
STA. 20+00		TO STA. 21+10		
FED. ROAD DIST. NO.		MILEAGE		FED. AID PROJECT

STA 21+10 (Q ENTR. LT.)
 ORIGINAL EL. = 912.33
 DESIGN EL. = 912.37
 DESIGN EARTHWORK
 FILL AREA = 2.00
 CUT AREA = 15.65

NOTE: END NEW BASE
 STA. 21+00

STA 20+93 (Q ENTR. RT.)
 ORIGINAL EL. = 911.97
 DESIGN EL. = 912.01
 DESIGN EARTHWORK
 FILL AREA = 0.61
 CUT AREA = 43.80

STA 20+50
 ORIGINAL EL. = 911.36
 DESIGN EL. = 911.40
 DESIGN EARTHWORK
 FILL AREA = 7.35
 CUT AREA = 32.69

STA 20+10
 ORIGINAL EL. = 911.21
 DESIGN EL. = 911.20
 DESIGN EARTHWORK
 FILL AREA = 0.00
 CUT AREA = 31.96

LOW PT.
 STA. 20+08.71
 911.20

STA 20+00
 ORIGINAL EL. = 911.26
 DESIGN EL. = 911.21
 DESIGN EARTHWORK
 FILL AREA = 160.31
 CUT AREA = 32.83