



**REMOVAL OF EXISTING STRUCTURES
NO. 1**

BELVIDERE ROAD		
STA	OFFSET	EACH
296+18	X-OVER	1.00
Total		1.00

PIPE CULVERTS, TYPE 1 RCCP 34"

BELVIDERE ROAD		
STA	OFFSET	FT
296+18	X-OVER	64.00
Total		64.00

**PRECAST REINFORCED CONCRETE
FLARED END SECTIONS 54"**

BELVIDERE ROAD		
STA	OFFSET	EA
296+13.81	RT	1.00
296+21.11	LT	1.00
Total		2.00

PIPE CULVERTS, SPECIAL 30"

BELVIDERE ROAD			
STA	OFFSET	30" RCCP (FT)	30" RC-EQRS (FT)
112+00.64	RT		3.00
112+00.64	LT		4.00
117+10.39	RT	4.00	
117+10.40	LT	8.00	
Total		12.00	7.00

**PRECAST REINFORCED CONCRETE
FLARED END SECTIONS 30"**

BELVIDERE ROAD		
STA	OFFSET	EA
117+10.39	RT	1.00
117+10.39	LT	1.00
Total		2.00

**PRECAST REINFORCED CONCRETE
FLARED END SECTIONS - ELLIPTICAL,
EQUIVALENT ROUND-SIZE 30"**

BELVIDERE ROAD		
STA	OFFSET	EA
112+00.64	RT	1.00
112+00.64	LT	1.00
Total		2.00

PIPE CULVERTS, SPECIAL 36"

BELVIDERE ROAD		
STA	OFFSET	36" RC-EQRS (FT)
337+55.72	RT	4.00
337+55.25	LT	4.00
346+61.04	RT	4.00
346+59.72	LT	4.00
Total		16.00

**PRECAST REINFORCED CONCRETE
FLARED END SECTIONS - ELLIPTICAL,
EQUIVALENT ROUND-SIZE 36"**

BELVIDERE ROAD		
STA	OFFSET	EA
337+55.72	RT	1.00
337+55.25	LT	1.00
346+61.04	RT	1.00
346+59.72	LT	1.00
Total		4.00

**STEEL PLATE BEAM GUARD RAIL,
TYPE A**

BELVIDERE ROAD		
STA	OFFSET	FT
212+78 TO 213+78	RT	87.50
215+83 TO 216+58	LT	68.75
320+82 TO 321+82	RT	175.00
322+96 TO 323+59	LT	118.75
Total		450.00

**TRAFFIC BARRIER TERMINAL
TYPE 1, SPECIAL (TANGENT)**

BELVIDERE ROAD		
STA	OFFSET	EA
212+43 TO 212+93	RT	1.00
213+87 TO 214+37	LT	1.00
215+40 TO 215+90	RT	1.00
216+47 TO 216+97	LT	1.00
320+14 TO 320+64	RT	1.00
320+82 TO 321+32	LT	1.00
323+45 TO 323+95	RT	1.00
323+59 TO 324+09	LT	1.00
Total		8.00

GUARDRAIL REMOVAL

BELVIDERE ROAD		
STA	OFFSET	FT
111+78 TO 112+36	LT	58.0
111+60 TO 112+18	RT	58.0
116+95 TO 117+48	LT	53.0
116+70 TO 117+23	RT	53.0
295+96 TO 296+53	LT	57.0
295+79 TO 296+38	RT	59.0
337+32 TO 337+85	LT	53.0
337+21 TO 337+74	RT	53.0
346+41 TO 346+93	LT	52.0
346+25 TO 346+77	RT	52.0
Total		548.0

**REMOVE AND RE-ERECT STEEL PLATE
BEAM GUARD RAIL**

BELVIDERE ROAD		
STA	OFFSET	FT
213+78 TO 215+51	RT	175.00
214+10 TO 215+83	LT	175.00
321+82 TO 322+90	RT	106.25
321+88 TO 322+96	LT	106.25
Total		562.5

**TERMINAL MARKER - DIRECT
APPLIED**

BELVIDERE ROAD		
STA	OFFSET	EA
212+43	RT	1.00
213+87	LT	1.00
215+90	RT	1.00
216+97	LT	1.00
320+14	RT	1.00
320+82	LT	1.00
323+95	RT	1.00
324+09	LT	1.00
Total		8.00

**BIDIRECTIONAL GUARD RAIL
REFLECTORS**

BELVIDERE ROAD		
STA	OFFSET	EA
212+43 TO 215+90	RT	4.00
213+87 TO 216+97	LT	4.00
320+14 TO 323+95	RT	4.00
320+82 TO 324+09	LT	4.00
Total		16.00

**THERMOPLASTIC PAVEMENT
MARKING - LINE 4"**

BELVIDERE ROAD	
STA	FT
101+36.14 TO 173+74.40	28,953.00
177+62.41 TO 351+42.13	52,936.00
Total	81,889.00

**THERMOPLASTIC PAVEMENT
MARKING - LINE 24"**

BELVIDERE ROAD	
STA	FT
PEARL STREET	24.00
VINE STREET	12.00
THOMPSON DRIVE	12.00
GENEVA DRIVE	12.00
APPLEGATE ROAD	12.00
HAMBORG ROAD	12.00
HAWTHORNE RIDGE	12.00
COUNTRY KNOLLS DRIVE	12.00
ATWOOD ROAD	12.00
SWANSON ROAD	12.00
BROWN ROAD	12.00
PICKEN ROAD	12.00
IL-173	12.00
Total	168.00

**RAISED REFLECTIVE PAVEMENT
MARKER**

BELVIDERE ROAD	
STA	EA
101+36.14 TO 173+74.40	91.00
177+62.41 TO 351+42.13	229.00
Total	320.00

RUMBLE STRIP

BELVIDERE ROAD		
STA	O/S	AREA (SF)
341+98	RT	275.0
346+29	RT	275.0
348+29	RT	275.0
Total		825.0