89370

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6579	05-00035-00-RP	PEORIA	31	3
STA.	TO STA.			
FED. ROAD DIST. NO. 4	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE J000	I000		
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	30	30.0			
20200100	EARTH EXCAVATION	CU YD	1724	1724.0			
20800150	TRENCH BACKFILL	CU YD	147	147.1			
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	2093	2092.9			
25000210	SEEDING, CLASS 2A	ACRE	0.5	0.5			
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	45	45.0			
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	45	45.0			
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	45	45.0			
25100115	MULCH, METHOD 2	ACRE	0.5	0.5			
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	50	50.0			
28000300	TEMPORARY DITCH CHECKS	EACH	4	4			
28000500	INLET AND PIPE PROTECTION	EACH	7	7			
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.7	0.7			
40600300	AGGREGATE (PRIME COAT)	TON	1	1			
40600990	TEMPORARY RAMP	SQ YD	80	64.0	16.0		
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	17		16.4		
40701841	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 8"	SQ YD	85		84.2		
42000401	PORTLAND CEMENT CONCRETE PAVEMENT 9" (JOINTED)	SQ YD	3676	3675.9			
42001300	PROTECTIVE COAT	SQ YD	4316	4316.0			
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT 6 INCH	SQ YD	182	181.4			
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT 8 INCH	SQ YD	345	344.5			
42400100	PORTLAND CEMENT CONCRETE SIDEWALK, 4 "	SQ FT	4272	4272.0			
44000100	PAVEMENT REMOVAL	SQ YD	3818	3701.0	117.0		
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	131		131.0		
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	54	53.3			
48101500	AGGREGATE SHOULDERS, TYPE B, 6"	SQ YD	384	384.0			
48300200	PORTLAND CEMENT CONCRETE SHOULDER 8"	SQ YD	208	207.5			
50105220	PIPE CULVERT REMOVAL	FOOT	429	429.0			
54207780	PIPE CULVERTS, TYPE 1, CORRUGATED STEEL OR ALUMINUM, EQUIVALENT ROUND-SIZE 15"	FOOT	85	85.0			
54207783	PIPE CULVERTS, TYPE 1, CORRUGATED STEEL OR ALUMINUM, EQUIVALENT ROUND-SIZE 18"	FOOT	60	60.0			
54215760	METAL END SECTIONS, EQUIVALENT ROUND-SIZE, 15"	EACH	4	4			
54215763	METAL END SECTIONS, EQUIVALENT ROUND-SIZE, 18"	EACH	2	2			
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	207	207.0			
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	168	168.0			
60219000	MANHOLES, TYPE A, 4'-DIAMETER, WITH TYPE 8 GRATE	EACH	1	1			
60220230	MANHOLES, TYPE A, 4'-DIAMETER, WITH SPECIAL FRAME AND GRATE	EACH	2	2			

SUMMARY OF QUANTITIES

	CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE J000	I000		
	60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	1	1			
	60238700	INLETS, TYPE A, WITH SPECIAL FRAME AND GRATE	EACH	2	2			
	60255500	MANHOLES TO BE ADJUSTED	EACH	5	5			
	60600095	CLASS SI CONCRETE (OUTLET)	CU YD	21.1	21.1			
	60602900	CONCRETE GUTTER, TYPE B (MODIFIED)	FOOT	859	859.0			
	60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	110	110.0			
	66410410	CHAIN LINK FENCE TO BE RELOCATED	FOOT	58	58.0			
	67100100	MOBILIZATION	L SUM	1	1			
	70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1	1			
*	78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	316	316.0			
*	78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	20	20.0			
	XX005089	BITUMINOUS DRIVEWAY PAVEMENT, 6"	SQ YD	270	150.0	119.6		
	XX005432	STORM SEWER, TYPE 2, WATER MAIN QUALITY PIPE, 18"	FOOT	304	304.0			
	Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1			
	Z0018700	DRAINAGE STRUCTURE TO BE REMOVED	EACH	1		1		
	Z0019500	DRYWELL	EACH	3	3			
	Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1		1		
	Z0076100	TRACK REMOVAL	FOOT	100		100.0		

* SPECIALTY ITEMS

REVISIONS NAME	DATE
	1/16/07

ILLINOIS DEPARTMENT OF TRANSPORTATION

MOFFITT STREET IMPROVEMENTS
SUMMARY OF QUANTITIES

DRAWN BY DLC
DATE 12/05/06 CHECKED BY REW

PM 27 08 '07 15:07 dgn