

89310

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6579	05-00035-00-RF	PEORIA	31	6
STA.		TO STA.		
FED. ROAD DIST. NO. 4		ILLINOIS FED. AID PROJECT		

AGGREGATE SHOULDERS SCHEDULE					AGGREGATE SHOULDERS, TYPE B, 6"
LOCATION					SQ YD
MOFFITT					
STA. 10+79.00	TO	STA. 10+98.00	LT		8.44
STA. 11+59.00	TO	STA. 12+50.00	LT		40.44
STA. 12+50.00	TO	STA. 12+57.00	LT		3.11
STA. 13+17.00	TO	STA. 15+05.00	LT		83.56
STA. 15+62.00	TO	STA. 16+02.00	LT		17.78
STA. 16+63.00	TO	STA. 17+50.00	LT		38.67
STA. 17+50.00	TO	STA. 18+82.00	LT		49.78
STA. 18+72.00	TO	STA. 19+64.00	LT		40.89
STA. 19+94.00	TO	STA. 22+20.00	LT		101.33
SUBTOTAL					384.00
TOTAL					384

STORM SEWER SCHEDULE												
LOCATION					TRENCH BACKFILL	STORM SEWERS, CLASS A		STORM SEWERS, WATER MAIN QUALITY	MAN TA 4 DIA W/ SPL F+G	MAN TA 4 DIA W/ TYPE B GRATE	INLETS, TYPE A, TYPE B GRATE	INLETS, TYPE A, W/ SPL F+G
MOFFITT					CU YD	TYPE 1		TYPE 2	EA	EA	EA	EA
						12"	18"	18"				
					FT	FT	FT					
STA. 12+50.00	RT	TO	STA. 14+75.00	RT	64.0			224.0				
STA. 14+75.00	RT	TO	STA. 14+75.00	LT	19.6			40.0				
STA. 15+82.00	LT	TO	STA. 17+50.00	LT			168.0					
STA. 14+75.00	LT	TO	STA. 15+82.00	LT		107.0						
STA. 17+50.00	LT	TO	STA. 17+50.00	RT	21.8			40.0				
STA. 17+50.00	LT	TO	STA. 18+50.00	RT	41.7	100.0						
STA. 12+50.00	RT											1.0
STA. 14+75.00	RT								1.0			
STA. 15+82.00	LT									1.0		
STA. 17+50.00	RT											1.0
STA. 18+50.00	RT											1.0
STA. 21+94.00	RT											1.0
SUBTOTAL					147.1	207.0	168.0	304.0	2	1	1	2
TOTAL					147.0	207.0	168.0	304.0	2	1	1	2

AGGREGATE = 2.05 TON/CU YD

PIPE CULVERT, CORRUGATED STEEL OR ALUMINUM, EQUIVALENT ROUND-SIZE										METAL END SECTIONS, EQUIVALENT ROUND-SIZE					
LOCATION										TYPE 1		15"		18"	
ST										15"	18"	15"	18"		
										FT	FT	EA	EA		
STA. 11+01.50	25.50 ft	LT	TO	STA. 11+53.50	25.50 ft	LT									
STA. 19+62.00	29.00 ft	LT	TO	STA. 19+95.00	27.00 ft	LT									
STA. 11+01.50	25.50 ft	LT									1.0				
STA. 11+53.50	25.50 ft	LT									1.0				
STA. 19+62.00	29.00 ft	LT									1.0				
STA. 19+95.00	27.00 ft	LT									1.0				
STA. 12+57.00	24.50 ft	LT	TO	STA. 13+17.00	24.50 ft	LT				60.0					
STA. 12+57.00	24.50 ft	LT												1.0	
STA. 13+17.00	24.50 ft	LT												1.0	
SUBTOTAL										85.0	60.0	4.0	2.0		
TOTAL										85.0	60.0	4.0	2.0		

CURB AND GUTTER SCHEDULE									
LOCATION					CU YD	CONCRETE GUTTER, TYPE B (MODIFIED)	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24		
MOFFITT						FOOT	FOOT		
STA. 10+00.00	TO	STA. 10+55.00	LT				55.00		
STA. 10+00.00	TO	STA. 10+55.00	RT				55.00		
STA. 10+55.00	TO	STA. 10+84.00	RT			29.00			
		STA. 10+93.4	RT.		1.72				
STA. 11+02.00	TO	STA. 11+64.00	RT			62.00			
		STA. 11+70.6	RT.		1.72				
STA. 11+77.00	TO	STA. 12+50.00	RT			73.00			
STA. 12+50.00	TO	STA. 12+73.00	RT			23.00			
		STA. 12+93.4	RT.		2.80				
STA. 13+14.00	TO	STA. 14+09.00	RT			95.00			
		STA. 14+22.7	RT.		2.80				
STA. 14+36.00	TO	STA. 15+05.00	RT			69.00			
		STA. 15+33.3	RT.		3.79				
STA. 15+62.00	TO	STA. 16+03.00	RT			41.00			
		STA. 16+32.1	RT.		3.79				
STA. 16+60.00	TO	STA. 16+98.00	RT			38.00			
		STA. 17+18.6	RT.		1.99				
STA. 17+37.00	TO	STA. 17+50.00	RT			13.00			
STA. 17+50.00	TO	STA. 18+53.00	RT			103.00			
STA. 18+63.00	TO	STA. 20+90.00	RT			227.00			
		STA. 20+97.7	RT.		1.99				
STA. 21+06.00	TO	STA. 21+92.00	RT			86.00			
		STA. 21+92	RT.		.46				
SUBTOTAL					21.06	859.00	110.00		
TOTAL					21.1	859	110		

MANHOLE TO BE ADJUSTED					
LOCATION					EACH
MOFFITT					
STA. 10+04.00	25.0 ft	RT			1.00
STA. 14+91.00	2.0 ft	RT			1.00
STA. 17+95.00	6.0 ft	RT			1.00
STA. 21+52.00	10.0 ft	RT			1.00
STA. 22+45.00	10.0 ft	RT			1.00
SUBTOTAL					5.00
TOTAL					5

MOBILIZATION SCHEDULE	
LOCATION	MOBILIZATION L. SUM
ENTIRE PROJECT	1
SUBTOTAL	1
TOTAL	1

CHAIN LINK FENCE TO BE RELOCATED SCHEDULE			
LOCATION			FOOT
RT. STA. 20+28	TO	RT. STA. 20+86	58.0
SUBTOTAL			58.0
TOTAL			58

TRAFFIC CONTROL AND PROTECTION SCHEDULE	
LOCATION	TRAFFIC CONTROL AND PROTECTION L. SUM
ENTIRE PROJECT	1
SUBTOTAL	1
TOTAL	1

PERMANENT PAINT PAVEMENT MARKING SCHEDULE						
LOCATION					PAINT PAVEMENT MARKING - LINE 4"	PAINT PAVEMENT MARKING - LINE 24"
					YEL. SKIP	WHITE
					FT	FT
MOFFITT						
STA. 9+27.00	CL	LT	TO	STA. 21+90.00	CL	20.0
STA. 9+27.00	CL	TO				316.0
SUBTOTAL					316.0	20.0
TOTAL					316	20

DRYWELL SCHEDULE					
LOCATION					DRYWELL EACH
STA. 14+75.00	25.00 ft	LT			1
STA. 17+50.00	23.50 ft	LT			1
STA. 19+02.00	15.00 ft	RT			1
SUBTOTAL					3
TOTAL					3

RAILROAD PROTECTIVE LIABILITY INSURANCE SCHEDULE	
LOCATION	RAILROAD PROTECTIVE LIABILITY INSURANCE L. SUM
ENTIRE PROJECT	1
SUBTOTAL	1
TOTAL	1

CONSTRUCTION LAYOUT SCHEDULE	
LOCATION	CONSTRUCTION LAYOUT L. SUM
ENTIRE PROJECT	1
SUBTOTAL	1
TOTAL	1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
MOFFITT STREET IMPROVEMENTS
SCHEDULE OF QUANTITIES
 DATE 12/05/06
 DRAWN BY DLG
 CHECKED BY REY