

CODE NO.	ITEM	CONSTRUCTION TYPE CODE 1000-2A	UNIT	TOTAL
20200100	EARTH EXCAVATION		CU YD	5,286
20201500	SUB-BASE GRANULAR MATERIAL, TYPE B		TON	200
20800150	TRENCH BACKFILL		CU YD	180
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION		SQ YD	300
21101505	TOPSOIL EXCAVATION AND PLACEMENT		CU YD	420
21400100	GRADING AND SHAPING DITCHES		FOOT	1,000
25000100	SEEDING, CLASS 1		ACRE	1.2
25000110	SEEDING, CLASS 1A		ACRE	1.9
25000400	NITROGEN FERTILIZER NUTRIENT		POUND	279
25000500	PHOSPHORUS FERTILIZER NUTRIENT		POUND	279
25000600	POTASSIUM FERTILIZER NUTRIENT		POUND	279
25100115	MULCH, METHOD 2		ACRE	3.1
25100630	EROSION CONTROL BLANKET		SQ YD	55
28000250	TEMPORARY EROSION CONTROL SEEDING		POUND	310
28000300	TEMPORARY DITCH CHECKS		EACH	9
28000400	PERIMETER EROSION BARRIER		FOOT	1,520
28000500	INLET AND PIPE PROTECTION		EACH	41
28100825	STONE DUMPED RIPRAP, CLASS B3		TON	19
28200200	FILTER FABRIC		SQ YD	28
30200750	PROCESSING MODIFIED SOIL 14"		SQ YD	8,375
30201500	LIME		TON	195
35100100	AGGREGATE BASE COURSE, TYPE A		TON	1,425
35600716	HOT-MIX ASPHALT BASE COURSE WIDENING, 10"		SQ YD	300
40200800	AGGREGATE SURFACE COURSE, TYPE B		TON	55
40600100	BITUMINOUS MATERIALS (PRIME COAT)		GAL	827
40600300	AGGREGATE (PRIME COAT)		TON	22
40600990	TEMPORARY RAMP		SQ YD	111
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50		TON	2,340
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50		TON	760
40800010	BITUMINOUS MATERIALS (PRIME COAT)		GAL	16
40800030	AGGREGATE (PRIME COAT)		TON	1
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING		TON	6
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH		SQ YD	94
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH		SQ YD	865
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH		SQ FT	6,305
42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH		SQ FT	305
42400410	PORTLAND CEMENT CONCRETE SIDEWALK 8 INCH		SQ FT	125
42400800	DETECTABLE WARNINGS		SQ FT	40
44000400	GUTTER REMOVAL		FOOT	30
44000500	COMBINATION CURB AND CUTTER REMOVAL		FOOT	20
44000600	SIDEWALK REMOVAL		SQ FT	50
542A0220	PIPE CHAMBERS, CLASS A, TYPE 1 15"		FOOT	132
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"		EACH	5
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"		EACH	1
54213666	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 21"		EACH	1
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"		EACH	1
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"		FOOT	611

CODE NO.	ITEM	UNIT	TOTAL
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	459
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	456
550A0110	STORM SEWERS, CLASS A, TYPE 1 21"	FOOT	454
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	84
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	196
55100300	STORM SEWER REMOVAL 8"	FOOT	30
60218300	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	7
60221000	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	4
60234200	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID	EACH	1
60236200	INLETS, TYPE A, TYPE B GRATE	EACH	5
60241900	INLETS, TYPE G-1, SPECIAL	EACH	21
60255500	MANHOLES TO BE ADJUSTED	EACH	4
60266600	VALVE BOXES TO BE ADJUSTED	EACH	4
60500040	REMOVING MANHOLES	EACH	1
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	3
60603450	GUTTER INLET (SPECIAL)	EACH	2
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	4,580
60609200	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.12	FOOT	38
60610400	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24	FOOT	32
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	50
61133100	FIELD TILE JUNCTION VAULTS, 2' DIA.	EACH	2
61133200	FIELD TILE JUNCTION VAULTS, 3' DIA.	EACH	2
61139900	STORM SEWERS, SPECIAL 6"	FOOT	100
61140000	STORM SEWERS, SPECIAL 8"	FOOT	100
61140100	STORM SEWERS, SPECIAL 10"	FOOT	100
61140200	STORM SEWERS, SPECIAL 12"	FOOT	100
70103700	TRAFFIC CONTROL COMPLETE	L SUM	1
70300200	TEMPORARY PAVEMENT MARKING	FOOT	3,631
70300210	TEMPORARY PAVEMENT MARKING-LETTERS & SYMBOLS	SQ FT	593
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	990
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	312
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	5,612
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	759
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	426
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	54
78001100	PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	44
78001140	PAINT PAVEMENT MARKING - LINE 8"	FOOT	71
78001150	PAINT PAVEMENT MARKING - LINE 12"	FOOT	32
X5504200	DUCTILE IRON STORM SEWER, 12 INCH	FOOT	18
X8950810	REMOVE AND RE-ERECT FLASHING BEACON	EACH	1
XX004817	STORM SEWER DUCTILE IRON PIPES CLASS 50 16"	FOOT	79
XX006473	STORM SEWER DUCTILE IRON PIPES CLASS 50 24"	FOOT	84
XX006499	INLET-MANHOLE TYPE G-1 5' DIAMETER	EACH	2
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	200
67100100	MOBILIZATION	L SUM	1
	* SPECIALTY ITEMS		

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SH. N.
	05-00030-01-FP	*	44	
STA. 67+20.50		TO STA. 89+83.95		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
* FULTON & PEORIA				
CONTRACT NO. 89395				

CITY OF FARMINGTON, ILLINOIS  
LIGHTFOOT ROAD - 2400E  
SECTION 05-00030-01-FP

SUMMARY OF QUANTITIES

DRAWN BY DRR	Farnsworth GROUP 2700 McGraw Drive	FILE # 24-7
DATE 11/06/06		BOOK # PEO-