


SUMMARY OF QUANTITIES

PAY CODE	PAY ITEM	UNITS	80%/20% IDOT/CITY FUNDING QUANTITY Y068	100% CITY FUNDING QUANTITY 100% LOCAL	TOTAL QUANTITY
20800150	TRENCH BACKFILL	CU YD	274.0	2,131.0	2,405.0
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	10,768.0	0.0	10,768.0
31101200	SUBBASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	10,768.0	0.0	10,768.0
35300300	PORTLAND CEMENT CONCRETE BASE COURSE 8"	SQ YD	9,710.0	129.0	9,839.0
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	26.0	7.0	33.0
40603335	HOT MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	42.0	11.0	53.0
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	997.0	0.0	997.0
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	5,196.0	1,680.0	6,876.0
42400460	PORTLAND CEMENT CONCRETE SIDEWALK 8 INCH, SPECIAL	SQ FT	210.0	0.0	210.0
42400800	DETECTABLE WARNINGS	SQ FT	88.0	0.0	88.0
44000100	PAVEMENT REMOVAL	SQ YD	38.0	129.0	167.0
44000159	HOT MIX ASPHALT SURFACE REMOVAL, 2.5'	SQ YD	372.0	0.0	372.0
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	745.0	0.0	745.0
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	5,127.0	0.0	5,127.0
44000600	SIDEWALK REMOVAL	SQ FT	5,316.0	1,680.0	6,996.0
44004400	PAVEMENT REMOVAL (SPECIAL)	SQ YD	9,380.0	0.0	9,380.0
55080050	STORM SEWERS, CLASS B, TYPE 1 12"	FOOT	770.0	0.0	770.0
55080090	STORM SEWERS, CLASS B, TYPE 1 18"	FOOT	219.0	0.0	219.0
55080120	STORM SEWERS, CLASS B, TYPE 1 24"	FOOT	188.0	0.0	188.0
* 56100600	PVC WATER MAIN 6"	FOOT	0.0	313.0	313.0
* 56100700	PVC WATER MAIN 8"	FOOT	0.0	2,631.0	2,631.0
* 56104900	WATER VALVES 6"	EACH	0.0	12.0	12.0
* 56105000	WATER VALVES 8"	EACH	0.0	6.0	6.0
* 56400500	FIRE HYDRANTS TO BE REMOVED	EACH	0.0	7.0	7.0
* 56400600	FIRE HYDRANTS	EACH	0.0	7.0	7.0
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	6.0	0.0	6.0
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1.0	0.0	1.0
60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1.0	0.0	1.0
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	25.0	0.0	25.0
60240220	INLETS, TYPE B, TYPE 3 FRAME AND GRATE	EACH	7.0	0.0	7.0
60241800	INLETS, TYPE G-1	EACH	2.0	0.0	2.0
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	1.0	0.0	1.0
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	8.0	0.0	8.0
60500040	REMOVING MANHOLES	EACH	1.0	0.0	1.0
60500060	REMOVING INLETS	EACH	13.0	0.0	13.0
60604400	COMBINATION CONCRETE CURB AND GUTTER, TB6, 18"	FOOT	5,127.0	0.0	5,127.0
67100100	MOBILIZATION	L. SUM	0.8	0.2	1.0
70101700	TRAFFIC CONTROL AND PROTECTION	L. SUM	0.8	0.2	1.0
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	505.0	0.0	505.0
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	168.0	0.0	168.0
* 78000100	THERMOPLASTIC PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	16.0	0.0	16.0
* 78000200	THERMOPLASTIC PAVEMENT MARKING-LINE 4"	FOOT	128.0	0.0	128.0
* 78000400	THERMOPLASTIC PAVEMENT MARKING-LINE 6"	FOOT	185.0	0.0	185.0
* 78000500	THERMOPLASTIC PAVEMENT MARKING-LINE 8"	FOOT	64.0	0.0	64.0
* 78000600	THERMOPLASTIC PAVEMENT MARKING-LINE 12"	FOOT	48.0	0.0	48.0
* 78001100	PAINT PAVEMENT MARKINGS-LETTERS AND SYMBOLS	SQ FT	47.0	0.0	47.0
* 78001110	PAINT PAVEMENT MARKING-LINE 4"	FOOT	1,298.0	0.0	1,298.0
* 78001140	PAINT PAVEMENT MARKING-LINE 8"	FOOT	137.0	0.0	137.0
* 88600100	DETECTOR LOOP, TYPE 1	FOOT	348.0	0.0	348.0
Δ 20013798	CONSTRUCTION LAYOUT	L. SUM	1.0	0.0	1.0
Δ 20076600	TRAINEES	HOURS	500.0	0.0	500.0
K1005863	TREE ROOT PRUNING	EACH	11.0	0.0	11.0
K1005881	TREE TRUNK PROTECTION	EACH	2.0	0.0	2.0
XX002873	BRICK SIDEWALK REMOVAL	SQ FT	584.0	0.0	584.0
* XX003345	WATER MAIN ENCASEMENT	FOOT	0.0	665.0	665.0
* X0323171	DI WM BEND 45 6"	EACH	0.0	1.0	1.0
* X0323185	DI WAT MN TEE, 6X6	EACH	0.0	1.0	1.0
* X0323186	DI WAT MN TEE, 8X6	EACH	0.0	14.0	14.0
* X0469600	CONNECTION TO EXISTING WATER MAIN	EACH	0.0	5.0	5.0
XX006791	BRICK DRIVEWAY PAVEMENT	SQ YD	84.0	0.0	84.0
XX006792	BRICK DRIVEWAY REMOVAL	SQ YD	79.0	0.0	79.0
XX006793	BRICK SIDEWALK	SQ FT	385.0	0.0	385.0
XX006794	BRICK WEARING SURFACE	SQ YD	9,671.0	0.0	9,671.0
XX006795	CONCRETE HEADER	EACH	6.0	0.0	6.0
* XX006796	DI WM BEND 90 6"	EACH	0.0	6.0	6.0
* XX006797	SERVICE CONNECTION & CURB STOP, SHORT SIDE, TYPE 1	EACH	0.0	46.0	46.0
* XX006798	SERVICE CONNECTION & CURB STOP, LONG SIDE, TYPE 1	EACH	0.0	9.0	9.0
* XX006799	SERVICE CONNECTION & CURB STOP, LONG SIDE, TYPE 2	EACH	0.0	30.0	30.0
* XX006800	LEAD WATER SERVICE REPLACEMENT	FOOT	0.0	1,650.0	1,650.0
* XX006801	GALVANIZED WATER SERVICE REPLACEMENT	FOOT	0.0	900.0	900.0
* XX006802	METER CONNECTION	EACH	0.0	75.0	75.0
* XX006803	EARTH EXCAVATION & EMBANKMENT	L. SUM	1.0	0.0	1.0
* XX006804	D. I. TAPPING SLEEVE & VALVE 6X6	EACH	0.0	1.0	1.0

Δ Y080
* SPECIALTY ITEM

SECTION #	TOTAL SHEETS	SHEET NO.
06-00447-12-PV	50	2

SUMMARY OF QUANTITIES
 N. BROAD ST. BRICK RECONSTRUCTION
 SECTION # 06-00447-12-PV
 FAU ROUTE 6793
 FEDERAL PROJECT # TE-00D4(097)
 JOB # C-94-029-07
 CONTRACT # 89456



ALESBURG, ILLINOIS
Proud Past • Strong Future