

SCHEDULE OF QUANTITIES - CONTINUED

PLATE NO.	SECTION	DATE	BY	CHECK
FAS 507	*	Vermilion	54	4
*05-00154-00-BR				

56109210
WATER VALVES TO BE ADJUSTED

LOCATION	EACH
STA. 99+28 LT	1
STA. 100+22 RT	1
STA. 102+48 RT	1
STA. 108+32 LT	1
STA. 114+98 LT	1
STA. 112+02 LT	1
STA. 112+12 LT	1
TOTAL	7

60236200
INLETS, TYPE A, TYPE 8 GRATE

LOCATION	EACH
A-8, 13.4 LT STA. 112+50	1
TOTAL	1

60605000
COMBINATION CONCRETE CURB AND GUTTER

LOCATION	FOOT
RT STA. 99+46 TO STA. 99+88	57.8
LT STA. 99+81 TO STA. 99+91	43.3
LT STA. 100+102 TO STA. 107+45	759.1
RT STA. 100+110 TO STA. 107+45	747.8
LT STA. 108+110 TO STA. 111+65	379.9
RT STA. 108+110 TO STA. 112+33	42.3
LT STA. 111+94 TO STA. 112+53	62.8
TOTAL	2473

78001180
PAINT PAVEMENT MARKING - LINE 24"

LOCATION	FOOT
STOP BARS	
@ NORTHVIEW - WEST	11
@ NORTHVIEW - EAST	10
@ WAYNE	2
TOTAL	33

56400710
FIRE HYDRANT AND VALVE (SPECIAL)

LOCATION	EACH
RT STA. 108+30.6	1
TOTAL	1

60240220
INLETS, TYPE B, TYPE 3 FRAME AND GRATE

LOCATION	EACH
B-3, 13.7 LT STA. 106+05	1
B-3, 13.7 RT STA. 106+16	1
B-3, 13.7 LT STA. 106+18	1
B-3, 13.7 RT STA. 108+20	1
B-3, 13.7 LT STA. 108+20	1
B-3, 13.7 RT STA. 111+80	1
B-3, 14.0 RT STA. 112+52	1
TOTAL	7

66502300
WOVEN WIRE FENCE REMOVAL

LOCATION	FOOT
LT STA. 105+22 TO STA. 107+22	200
LT STA. 105+25	25
LT STA. 108+04 TO STA. 108+17	33
LT STA. 108+62 TO STA. 108+65	66
TOTAL	304

X2010400
STUMP REMOVAL ONLY

LOCATION	UNIT
STA. 102+23, 27 LT	24
TOTAL	24

56400800
FIRE HYDRANT AND VALVE TO BE MOVED

LOCATION	EACH
STA. 99+51.5	1
TOTAL	1

60255500
MANHOLES TO BE ADJUSTED

LOCATION	EACH
STA. 98+98, 16.0 RT	1
STA. 108+33, 11.5 LT	1
STA. 109+18, 19.5 LT	1
STA. 109+46, 33.5 LT	1
TOTAL	4

66700205
PERMANENT SURVEY MARKERS, TYPE I

LOCATION	EACH
STA. 99+89 25.31' E SE CORNER, SW 1/4 SEC 27	1
STA. 113+21.02' S.W. NW CORNER, SW 1/4 OF SE 1/4 SEC 27	1
TOTAL	2

XX005742
DETECTABLE WARNING TILES

LOCATION	SQ FT
LT STA. 99+73 TO STA. 99+81	14
LT STA. 100+25 TO STA. 100+33	10
LT STA. 111+80 TO STA. 111+85	5
LT STA. 111+95 TO STA. 112+01	15
TOTAL	63

60218500
MANHOLES, TYPE A, 4' DIAMETER, TYPE 3 FRAME AND GRATE

LOCATION	EACH
A-3 (4'), 14.2 LT, STA. 102+70	1
A-3 (4'), 14.2 LT, STA. 103+82.5	1
A-3 (4'), 14.2 LT, STA. 108+01	1
A-3 (4'), 14.2 RT, STA. 109+02	1
A-3 (4'), 14.2 RT, STA. 110+18	1
A-3 (4'), 14.2 RT, STA. 111+22	1
TOTAL	6

SEE SPECIAL PROVISIONS FOR SANITARY VALVE VAULT

60500050
REMOVING CATCH BASINS

LOCATION	EACH
LT STA. 102+00.0	1
TOTAL	1

70300100
SHORT TERM PAVEMENT MARKING

LOCATION	SQ YD
STA. 99+17 TO STA. 113+00	180
TOTAL	180

X0322923
SEGMENTAL CONCRETE BLOCK WALL

LOCATION	SQ FT
LT STA. 103+56.75 TO STA. 104+00	391
LT STA. 104+10 TO STA. 104+36	351
TOTAL	732

60219000
MANHOLES, TYPE A, 4' DIAMETER, TYPE 8 GRATE

LOCATION	EACH
A-8 (4'), 33 LT, STA. 100+34.5	1
A-8 (4'), 35 LT, STA. 101+50	1
TOTAL	2

60600095
CLASS SI CONCRETE (OUTLET)

LOCATION	CY
RT STA. 99+46	0.35
LT STA. 99+56	0.35
LT STA. 99+91	0.35
RT STA. 28+19	0.35
RT STA. 100+0	0.35
LT STA. 100+1	0.35
LT STA. 112+33	0.35
RT STA. 112+33	0.35
TOTAL	2.8

78001110
PAINT PAVEMENT MARKING - LINE 4"

LOCATION	FOOT
YELLOW SKIP DASH STA. 99+17 TO STA. 113+00	390
WHITE EDGE LINES STA. 99+48 TO STA. 113+00	325
TOTAL	715

60235700
INLETS, TYPE A, TYPE 3 FRAME AND GRATE

LOCATION	EACH
A-3, 13.4 LT, STA. 100+48	1
A-3, 13.4 RT, STA. 103+32.5	1
A-3, 13.4 RT, STA. 105+01	1
A-3, 13.4 RT, STA. 108+05	1
A-3, 13.4 RT, STA. 109+02	1
A-3, 13.4 RT, STA. 110+18	1
A-3, 13.4 LT, STA. 111+22	1
TOTAL	7

DSGN	K.J. Hoffmann				
DR	K.J. Hoffmann				
CHK	J.A. Fraunhoffer				
APVD	J.A. Fraunhoffer	NO.	DATE	REVISION	BY

FRAUENHOFFER
Fraunhoffer and Associates, P.C. Consulting Engineers
3002 Crossing Court Champaign, IL 61822 217-351-6268

SCHEDULE OF QUANTITIES - SHEET 2 OF 3
VILLAGE OF CATLIN
SECTION 05-00154-00-BR
VERMILION COUNTY

SHEET	4
DATE	JUN 2005
PROJ. NO.	5022