

SECTION	SHEET	TOTAL SHEETS	PAGE NO.
FAS 507	Vermilion	54	5
*05-00154-00-BR			

SCHEDULE OF QUANTITIES - CONTINUED

Z0051500

REMOVING AND RESETTING STREET SIGNS	
LOCATION	EACH
NORTHVIEW INSR LOCATION	1
MAINE ISAKE LOCATION	1
TOTAL	2

Z0056700

SANITARY SEWER 4" FORCE MAIN	
LOCATION	FOOT
STA. 102+75 TO STA. 109+53	562
TOTAL	562

6" TAPPING SLEEVE & VALVE

LOCATION	EACH
10' LT STA. 99+51.5	1
10' RT STA. 109+23.7	1
TOTAL	2

SANITARY PUMP STATION ADJUSTMENTS

LOCATION	SUM
STA. 108+34, 21' L.	1
TOTAL	1

REMOVE AND REPLACE EXISTING STONE WALL

LOCATION	SQ FT
RT STA. 102+35 TO STA. 102+60	320
TOTAL	320

Z0200100, Z0400800, & Z101505

EARTHWORK	
ITEMS	CU YD
EARTH EXCAVATION	1,862
TOPSOIL EXCAVATION	232
TOTAL CUT	2,094
EMBANKMENT	4,169
TOP SOIL PLACEMENT	179
TOTAL FILL	4,347
FURNISHED EXCAVATION = (FILL EXCAVATION / 1.25) + 1.25	3,341
TOPSOIL EXCAVATION AND PLACEMENT TOTAL	179
for excavation and placement balance using 6" depth	

NOTE: 25% SHRINKAGE FACTOR WAS USED

	56200300	Z0015000	56201400	Z08001500
	1" WATER SERVICE LINE	CURB STOPS	CORROSION STOPS	TRENCH BACKFILL
LOCATION	FOOT	EACH	EACH	CU YD
RT STA. 100+50	52	1	1	3.7
LT STA. 100+75	13	1	1	0.9
RT STA. 102+47	8	1	1	0
LT STA. 103+50	64	1	1	4.4
TOTAL	137	4	4	9

42300200, 42300400

40200800

LOCATION	PCC OFFSETS	PCC DRIVEWAY PAVEMENT 6" THICK 8" THICK	AGGREGATE OFFSETS	AGGREGATE SURFACE COURSE, TYPE
P.E. - LT STA. 100+35	B.O.C TO F.O.S	24.7	B.O.S TO 39' LT	10.5
P.E. - LT STA. 102+57	B.O.C TO F.O.S	6.0	B.O.S TO 45' LT	9.3
P.E. - LT STA. 103+84	B.O.C TO F.O.S	6.0	B.O.S TO 55' LT	25.0
P.E. - RT STA. 105+20	- TO -	-	B.O.S TO 69' R	31.3
C.E. - LT STA. 105+73	B.O.C TO F.O.S & B.O.C TO 30' LT	30.0	-	-
P.E. - RT STA. 109+51	B.O.C TO 24.5' R	33.0	24.5' RT TO 34' LT	6.4
P.E. - STA. 110+43	B.O.C TO F.O.S	4.0	B.O.S TO 29' LT	3.3
P.E. - RT STA. 111+42	B.O.S TO 24.5' R	8.0	24.5' RT TO 31' L	3.6
P.E. - RT STA. 112+13	B.O.C TO 24.5' R	27.3	24.5' RT TO 31' LT	6.4
TEMP. DRIVES	-	-	VARIOUS	55.0
		TOTAL	TOTAL	TOTAL
		109.0	30.0	250.0

DSGN	K.J. Hoffmann				
DR	K.J. Hoffmann				
CHK	J.A. Fraenhoffer				
APVD	J.A. Fraenhoffer	NO.	DATE	REVISION	BY

FRAUENHOPFER
 Fraenhoffer and Associates, P.C. Consulting Engineers
 3002 Crossing Court Champaign, IL 61822 217-351-6268

SCHEDULE OF QUANTITIES - SHEET 3 OF 3

VILLAGE OF CATLIN
 SECTION 05-00154-00-BR
 VERMILION COUNTY

SHEET	5
DWG NO.	5022-SCH.dwg
DATE	JUN 2006
PROJ NO.	5022