

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
473	05-00046-12-RP	McLEAN	32	5
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
CONTRACT NO. 91370				

EARTHWORK TABLE				
CH	FROM STATION	TO STATION	CUT YD	FILL YD
WEST OF I-55 BRIDGE	36+74.14	48+66.95	2110	0
EAST OF I-55 BRIDGE	51+32.51	63+99.57	2184	0
TEMPORARY HMA REMOVAL	36+74.14	63+99.57	253	0
EXISTING PIPE UNDERDRAIN REMOVAL	36+74.14	63+99.57	256	0

TOTAL EARTH EXCAVATION 4803 CY  
TOTAL FILL 0 CY  
TOTAL WASTE 4803 CY

SEEDING TABLE				
LOCATION	SEEDING, CLASS 1	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT
	ACRE	POUND	POUND	POUND
WBL STA 36+74.14 TO STA 42+80	0.14	12.6	12.6	12.6
WBL STA 44+00 TO STA 48+75	0.10	9.0	9.0	9.0
WBL STA 51+40 TO STA 55+95	0.10	9.0	9.0	9.0
WBL STA 56+80 TO STA 63+99.57	0.15	13.5	13.5	13.5
EBL STA 36+74.14 TO STA 43+10	0.15	13.5	13.5	13.5
EBL STA 44+10 TO STA 48+55	0.10	9.0	9.0	9.0
EBL STA 51+20 TO STA 55+95	0.10	9.0	9.0	9.0
EBL STA 57+20 TO STA 62+80	0.15	13.5	13.5	13.5
EBL STA 63+50 TO STA 63+99.57	0.01	0.9	0.9	0.9
TOTAL	1.0	90	90	90

PERIMETER EROSION BARRIER	
LOCATION	FOOT
WBL STA 39+75 TO STA 40+75	117
WBL STA 44+00 TO STA 45+00	101
WBL STA 55+00 TO STA 55+95	108
WBL STA 60+50 TO STA 63+99.57	358
EBL STA 39+75 TO STA 40+75	117
EBL STA 44+10 TO STA 45+00	98
EBL STA 55+00 TO STA 55+94	109
EBL STA 60+50 TO STA 62+80	242
EBL STA 63+50 TO STA 63+99.57	50
TOTAL	1300

SUB-BASE GRANULAR MATERIAL, TYPE A	
LOCATION	TON
WBL STA 36+74.14 TO STA 38+40	117
WBL STA 38+40 TO STA 48+66.95	664
WBL STA 43+63 TO STA 46+65	138
WBL STA 43+82.65 TO STA 44+41.81	14
WBL STA 46+65 TO STA 48+45	41
BRIDGE OMISSION STA 48+66.95 TO STA 51+32.51	
WBL STA 51+32.51 TO STA 61+50	657
WBL STA 61+50 TO STA 63+99.57	166
EBL STA 36+74.14 TO STA 38+40	91
EBL STA 38+40 TO STA 48+66.95	664
BRIDGE OMISSION STA 48+66.95 TO STA 51+32.51	
EBL STA 51+32.51 TO STA 63+99.57	818
EBL STA 51+65 TO STA 53+45	41
EBL STA 53+45 TO STA 56+37	133
EBL STA 55+57.58 TO STA 56+17.03	14
FROM CONCRETE MEDIAN SURFACE	654
FROM UNDERDRAIN REMOVAL	524
TOTAL	4735

SUB-BASE GRANULAR MATERIAL, (SPECIAL)	
LOCATION	TON
WBL STA 36+74.14 TO STA 38+40	117
WBL STA 38+40 TO STA 48+66.95	663
WBL STA 43+63 TO STA 46+65	138
WBL STA 43+82.65 TO STA 44+41.81	14
WBL STA 46+65 TO STA 48+45	41
BRIDGE OMISSION STA 48+66.95 TO STA 51+32.51	
WBL STA 51+32.51 TO STA 61+50	657
WBL STA 61+50 TO STA 63+99.57	166
EBL STA 36+74.14 TO STA 38+40	91
EBL STA 38+40 TO STA 48+66.95	663
BRIDGE OMISSION STA 48+66.95 TO STA 51+32.51	
EBL STA 51+32.51 TO STA 63+99.57	818
EBL STA 51+65 TO STA 53+45	41
EBL STA 53+45 TO STA 56+37	133
EBL STA 55+57.58 TO STA 56+17.03	14
FROM CONCRETE MEDIAN SURFACE	654
TOTAL	4210

PAVEMENT REMOVAL	
LOCATION	SO.YD.
WBL STA 36+74.14 TO STA 37+72	174
WBL STA 37+72 TO STA 48+66.95	1703
WBL STA 46+35 TO STA 48+66.95	155
WBL STA 43+63 TO STA 46+35	363
WBL STA 43+82 TO STA 44+42	40
BRIDGE OMISSION STA 48+66.95 TO STA 51+32.51	
WBL STA 51+32.51 TO STA 62+29	1706
WBL STA 62+29 TO STA 63+99.57	284
EBL STA 36+74.14 TO STA 37+72	141
EBL STA 37+72 TO STA 48+66.95	1704
BRIDGE OMISSION STA 48+66.95 TO STA 51+32.51	
EBL STA 51+32.51 TO STA 53+75	162
EBL STA 53+75 TO STA 56+35	347
EBL STA 55+57 TO STA 56+17	40
EBL STA 51+32.51 TO STA 63+99.57	1971
TOTAL	8790

AGGREGATE SHOULDERS, TYPE B	
LOCATION	TON
WBL STA 36+74.14 TO STA 42+80	61
WBL STA 44+00 TO STA 48+66.95	48
WBL STA 51+32.51 TO STA 56+00	48
WBL STA 56+85 TO STA 63+99.57	72
EBL STA 36+74.14 TO STA 43+10	64
EBL STA 44+00 TO STA 48+66.95	48
EBL STA 51+32.51 TO STA 56+00	48
EBL STA 57+35 TO STA 62+85	56
EBL STA 63+60 TO STA 63+99.57	5
TOTAL	450

COMBINATION CURB AND GUTTER REMOVAL	
LOCATION	FOOT
STA 38+81 TO STA 43+82 LT./RT.	1003
STA 44+42 TO STA 48+66.95 LT./RT.	851
BRIDGE OMISSION STA 48+66.95 TO STA 51+32.51	
STA 51+32.51 TO STA 55+58 LT./RT.	851
STA 56+17 TO STA 61+19 LT./RT.	1005
TOTAL	3710

MEDIAN REMOVAL	
LOCATION	SO. FT.
STA 37+72 TO STA 38+81	655
STA 38+81 TO STA 39+51	630
STA 39+51 TO STA 41+50	2389
STA 41+50 TO STA 43+30	2881
STA 43+30 TO STA 43+82	572
STA 44+42 TO STA 46+35	772
STA 46+35 TO STA 48+66.95	2320
BRIDGE OMISSION STA 48+66.95 TO STA 51+32.51	
STA 51+32.51 TO STA 53+75	2425
STA 53+75 TO STA 55+58	732
STA 56+17 TO STA 56+80	693
STA 56+80 TO STA 61+19	4391
TOTAL	18460

PAVED SHOULDER REMOVAL	
LOCATION	SO.YD.
WBL STA 36+74.14 TO STA 42+36.22	625
WBL STA 44+11.82 TO STA 48+66.95	507
BRIDGE OMISSION STA 48+66.95 TO STA 51+32.51	
WBL STA 51+32.51 TO STA 55+86.23	505
WBL STA 57+13.25 TO STA 62+29	574
WBL STA 62+29 TO STA 63+99.57	133
EBL STA 36+74.14 TO STA 42+76.03	670
EBL STA 44+16.98 TO STA 48+66.95	501
BRIDGE OMISSION STA 48+66.95 TO STA 51+32.51	
EBL STA 51+32.51 TO STA 55+94.06	513
EBL STA 57+67.08 TO STA 61+19	392
EBL STA 61+19 TO STA 62+49	123
EBL STA 63+85 TO STA 63+99.57	7
TOTAL	4550

HOT-MIX ASPHALT SHOULDERS	
LOCATION	TON
WBL STA 36+74.14 TO STA 42+36.22	288
WBL STA 44+11.82 TO STA 48+66.95	233
BRIDGE OMISSION STA 48+66.95 TO STA 51+32.51	
WBL STA 51+32.51 TO STA 55+85.23	232
WBL STA 57+13.25 TO STA 61+50	223
WBL STA 61+50 TO STA 63+99.57	89
EBL STA 36+74.14 TO STA 42+76.03	308
EBL STA 44+16.98 TO STA 48+66.95	231
BRIDGE OMISSION STA 48+66.95 TO STA 51+32.51	
EBL STA 51+32.51 TO STA 55+95	237
EBL STA 57+67.08 TO STA 61+50	196
EBL STA 61+50 TO STA 62+48	45
EBL STA 63+85 TO STA 63+99.57	3
TOTAL	2085

McLEAN COUNTY, ILLINOIS  
MFT SECTION 05-00046-12-RP

SCHEDULE OF QUANTITIES

DRAWN BY JJ		FILE NO. 24-7687
DATE 12/06/06		BOOK NO. 2416
CHECKED BY RGD	2700 McGraw Drive Bloomington, Illinois 61704 309.883-8435 / fax 309.883-1871	SHEET NO. 5 OF 32