

EA	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
152	(42X)I-3	SALINE	46	3
ST A.	TO STA.			
RD.	ROAD DIST. NO.	ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	CONSTRUCTION TYPE CODE
			J000-2A URBAN TOTAL QUANTITIES 80% FED 20% STATE
20200100	EARTH EXCAVATION	CU YD	911
20800150	TRENCH BACKFILL	CU YD	120
21101645	TOPSOIL, FURNISH AND PLACE, 12"	SQ YD	292
25000115	SEEDING, CLASS 1B	ACRE	0.34
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	40
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	40
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	40
25000700	AGRICULTURAL GROUND LIMESTONE	TON	0.7
25100630	EROSION CONTROL BLANKET	SQ YD	1627
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	68
28000300	TEMPORARY DITCH CHECKS	EACH	3
28100105	STONE RIPRAP, CLASS A3	SQ YD	8
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A, 4"	SQ YD	2097
35300500	PORTLAND CEMENT CONCRETE BASE COURSE, 10"	SQ YD	1542
40600115	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	GALLON	642
40600300	AGGREGATE (PRIME COAT)	TON	9
40600990	TEMPORARY RAMP	SQ YD	43
40600855	POLYMERIZED LEVELING BINDER(MACHINE METHOD) N105	TON	97
40603575	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX E, N105	TON	600
42001300	PROTECTIVE COAT	SQ YD	997
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7"	SQ YD	422
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8"	SQ YD	115
44000100	PAVEMENT REMOVAL	SQ YD	748
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	5594
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	761
44000500	AND COMBINATION CURB GUTTER REMOVAL	FOOT	1490
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	3831
50104400	CONCRETE HEADWALL REMOVAL	EACH	3
50105220	PIPE CULVERT REMOVAL	FOOT	159
50800105	REINFORCEMENT BARS	POUND	732
54002020	EXPANSION BOLTS 3/4 INCH	EACH	8
54003000	CONCRETE BOX CULVERT	CU YD	4.1
54207159	PIPE CULVERTS, TYPE 1, REINFORCED CONCRETE, ELLIPTICAL, EQUIVALENT ROUND-SIZE 24"	FOOT	41
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTION, 12"	EACH	5
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTION, 15"	EACH	3
54214719	PRECAST REINFORCED CONCRETE FLARED END SECTION - ELIPTICAL, EQUIVALENT ROUND-SIZE, 24"	EACH	2
542A0220	PIPE CULVERT, CLASS A, TYPE 1, 15"	FOOT	36

PLOT DATE = 12/15/2006
 FILE NAME = c:\p\projects\98944\98944.dwg
 PLOT SCALE = 50.0000 / IN
 USER NAME = harsop