CONTRACT NO. 98950

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	11
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* FAI 57 & FAU 9629 (OLD IL 13)
** (X1-6-2)VB-2, (X1-6)HBK-2

SUMMARY OF QUANTITIES

			COUNTY:	WILLIAMSON									
			LOCATION:	URBAN									
			ROUTE:	F. A. I. 57						FAU 9629 (OLD IL 13)			
			FUNDING:	90% FEDERAL/ 10 % STATE-ACIM						90% FED 10% STATE	100% STATE	90% FED 10% STATE	90% FED 10% CITY
			WORK TYPE:	ROADWAY	BRIDGE	BRIDGE	BRIDGE	BRIDGE	LIGHTING	SIGNALS	SIGNALS	ROADWAY	ROADWAY
				STA 1500+00 TO STA 1556+85	100-0084 100-0085	100-0086 100-0087	100-0008 100-0009	100-0005		SB I57 RAMPS ACIM	VA & NB I57 RAMPS	STA. 753+20 TO STA. 784+40 ACIM	STA. 753+20 TO STA. 784+40 ACIM
			CONSTRUCTION TYPE CODE:	I000-2A	X271-2A	X171-5B	SFTY-2A	SFTY-2A	Y030-1E	Y031-1F	Y031-1F	I000-2A	I000-2A
CODE NUMBER	ITEM DESCRIPTION	UNIT	QUANTITY										
48203100	HOT-MIX ASPHALT SHOULDERS	TON	1,153.0	1,104.0									49.0
48203023	HOT-MIX ASPHALT SHOULDERS, 6 1/2"	SQ YD	4235	4235									
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	8156	8004								152.0	
48203031	HOT-MIX ASPHALT SHOULDERS, 8 1/2"	SQ YD	86.0									86.0	
48203035	HOT-MIX ASPHALT SHOULDERS, 9 1/2"	SQ YD	1,610.0									1,610.0	
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1.0		1.0								
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1.0		1.0								
50100500	REMOVAL OF EXISTING STRUCTURES NO. 3	EACH	1.0			1.0							
50100600	REMOVAL OF EXISTING STRUCTURES NO. 4	EACH	1.0			1.0							
50100700	REMOVAL OF EXISTING STRUCTURES NO. 5	EACH	1.0									1.0	
50100800	REMOVAL OF EXISTING STRUCTURES NO. 6	EACH	1.0									1.0	
50102400	CONCRETE REMOVAL	CU YD	10.0	3.0								7.0	
50104400	CONCRETE HEADWALL REMOVAL	EACH	17.0	12.0								5.0	
50105220	PIPE CULVERT REMOVAL	FOOT	447.0	286.0								161.0	
50157300	PROTECTIVE SHIELD	SQ YD	1,276.0		711.0	565.0							
3 50104650	SLOPE WALL REMOVAL	SQ YD	820.0		820.0								
50200100	STRUCTURE EXCAVATION	CU YD	2,195.0		947.0	1,248.0							
50300100	FLOOR DRAINS	EACH	40.0		24.0	16.0							
50300225	CONCRETE STRUCTURES	CU YD	1,133.2		388.5	734.7							10.0
50300255	CONCRETE SUPERSTRUCTURE	CU YD	1,614.7	29.8	849.4	735.5							
50300260	BRIDGE DECK GROOVING	SQ YD	8,974.0	1,973.0	2,843.0	2,155.0	2,003.0						
50300280	CONCRETE ENCASEMENT	CU YD	37.9		17.5	20.4							
50300285	FORM LINER TEXTURED SURFACE	SQ FT	1,542.0		1,542.0								
50300300	PROTECTIVE COAT	SQ YD	7,765.0		3,218.0	2,450.0	2,097.0						
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1.0		0.70	0.30							
50500505	STUD SHEAR CONNECTORS	EACH	30,567.0		17,526.0	13,041.0							
50800105	REINFORCEMENT BARS	POUND	967.0										967.0
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	492,825.0	10,795.0	264,900.0	217,130							
50800515	BAR SPLICERS	EACH	3,096.0		1,624.0	1,472.0							
51100100	SLOPE WALL 4 INCH	SQ YD	1,845.0		1,620.0	225.0							
51100500	BITUMINOUS COATED AGGREGATE SLOPEWALL 6"	SQ YD	2,020.0			2,020.0							
51201600	FURNISHING STEEL PILES HP 12X53	FOOT	2,739.0		2,739.0								
51201800	FURNISHING STEEL PILES HP 14X73	FOOT	5,340.0			5,340.0							
51203600	TEST PILE STEEL HP 12X53	EACH	6.0		6.0								
51203800	TEST PILE STEEL HP 14X73	EACH	3.0			3.0							
51205200	TEMPORARY SHEET PILING	SQ FT	1,430.0		730.0	700.0							
51500100	NAME PLATES	EACH	4.0		2.0	2.0							
52000030	PREFORMED JOINT SEAL 2 1/2"	FOOT	427.0	120.0	174.0	133.0							
52100520	ANCHOR BOLTS, 1"	EACH	276.0		92.0	184.0							

3 Rev. 2-28-07

Rev.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

5 OF 12

SCALE: VERT. HORIZ.

DATE

DRAWN BY JCK

CHECKED BY

PLOT DATE = 12/14/2006
FILE NAME = c:\projects\98288\2\sdf3\sdf3schn32
PLOT SCALE = 50.0000 ' / IN.
USER NAME = kevanejk