

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	10
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

- * FAI 57 & FAU 9629 (OLD IL 13)
- ** XI-6-2(VB-2, XI-6)HBK-2

SUMMARY OF QUANTITIES

		WILLIAMSON URBAN											
		F. A. I. 57					FAU 9629 (OLD IL 13)						
		90% FEDERAL/ 10% STATE-ACIM					90% FED 10% STATE	100% STATE	90% FED 10% STATE	90% FED 10% CITY			
CODE NUMBER	ITEM DESCRIPTION	UNIT	QUANTITY	ROADWAY	BRIDGE	BRIDGE	BRIDGE	BRIDGE	LIGHTING	SIGNALS	SIGNALS	ROADWAY	ROADWAY
				STA 1500+00 TO STA 1556+85	100-0084 TO 100-0085	100-0086 TO 100-0087	100-0008 TO 100-0009	100-0005		SB 157 RAMP ACIM	VA & NB 157 RAMP	STA. 753+20 TO STA. 784+40 ACIM	STA. 753+20 TO STA. 784+40 ACIM
				I000-2A	X271-2A	X171-5B	SFTY-2A	SFTY-2A	Y030-1E	Y031-1F	Y031-1F	I000-2A	I000-2A
42000301	PORTLAND CEMENT CONCRETE PAVEMENT 8" (JOINTED)	SQ YD	661.0									661.0	
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD	4,853.0	4,389.0								464.0	
42001200	PAVEMENT FABRIC	SQ YD	183.0										183.0
42001300	PROTECTIVE COAT	SQ YD	15,304	10,990								3,120.0	1,188.0
42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ YD	2,073.0	2,073.0									
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	176.0									176.0	
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	172.0									172.0	
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	10,373.0										10,373.0
42400800	DETECTABLE WARNINGS	SQ FT	91.0										91.0
44000100	PAVEMENT REMOVAL	SQ YD	21,142	19,829								1,313.0	
44000169	HOT-MIX ASPHALT SURFACE REMOVAL, 5"	SQ YD	17,173.0	17,173.0									
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	2,519.0	2,519.0									
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	783.0									783.0	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	4404	784								3,620.0	
44001114	HOT-MIX ASPHALT SURFACE REMOVAL (ASBESTOS)	SQ YD	1,052.0				1,052.0						
44003800	MEDIAN SURFACE REMOVAL	SQ FT	13,428.0	642.0								12,786.0	
44004000	PAVED DITCH REMOVAL	FOOT	139.0	72.0								67.0	
44004250	PAVED SHOULDER REMOVAL	SQ YD	21,596.0	20,985.0								611.0	
44200970	CLASS B PATCHES, TYPE II, 10 INCH	SQ YD	488.0	6.0									482.0
44200974	CLASS B PATCHES, TYPE III, 10 INCH	SQ YD	17.0										17.0
44200976	CLASS B PATCHES, TYPE IV, 10 INCH	SQ YD	123.0										123.0
44201007	CLASS B PATCHES, TYPE II, 13 INCH	SQ YD	108.0										108.0
44201011	CLASS B PATCHES, TYPE III, 13 INCH	SQ YD	43.0										43.0
44212900	PAVEMENT PATCHING (PARTIAL DEPTH)	SQ YD	260.0										260.0
44213200	SAW CUTS	FOOT	3,851.0										3,851.0
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	1,253.0	1,253.0									
48100700	AGGREGATE SHOULDERS, TYPE A 8"	SQ YD	2229	2229									9.0
48101200	AGGREGATE SHOULDERS, TYPE B	TON	9.0										

PLOT DATE = 12/14/2006
 FILE NAME = c:\progra\win98\282\vol01\3\of3\sum32
 USER NAME = hroze

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

4 OF 12

SCALE: VERT. DRAWN BY JCK
 DATE: HORIZ. CHECKED BY