

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	12
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

COUNTY:	WILLIAMSON									
LOCATION:	URBAN									
ROUTE:	F. A. I. 57									
FUNDING:	90% FEDERAL/ 10% STATE-ACIM					FAU 9629 (OLD IL 13)				
WORK TYPES:	ROADWAY	BRIDGE	BRIDGE	BRIDGE	BRIDGE	LIGHTING	90% FED 10% STATE SIGNALS	100% STATE SIGNALS	90% FED 10% STATE ROADWAY	90% FED 10% CITY ROADWAY
	STA 1500+00 TO STA 1556+85	100-0084 100-0085	100-0086 100-0087	100-0008 100-0009	100-0005		SB I57 RAMP ACIM	VA & NB I57 RAMP	STA. 753+20 TO STA. 784+40 ACIM	STA. 753+20 TO STA. 784+40 ACIM
CONSTRUCTION TYPE CODE:	I000-2A	X271-2A	X171-5B	SFTY-2A	SFTY-2A	Y030-1E	Y031-1F	Y031-1F	I000-2A	I000-2A

CODE NUMBER	ITEM DESCRIPTION	UNIT	QUANTITY								
54001001	BOX CULVERT END SECTION, CULVERT NO. 1	EACH	1.0								1.0
54002060	EXPANSION BOLTS 3/4 INCH X 12 INCH	EACH	18.0	18.0							
54003000	CONCRETE BOX CULVERTS	CU YD	21.0	21.0							
54010804	PRECAST CONCRETE BOX CULVERT 8' X 4'	FOOT	83.0								83.0
542A0226	PIPE CULVERTS, CLASS A, TYPE 1 21"	FOOT	38.0								38.0
542A1069	PIPE CULVERTS, CLASS A, TYPE 2 24"	FOOT	146.0	146.0							
542A1081	PIPE CULVERTS, CLASS A, TYPE 2 36"	FOOT	88.0	88.0							
542A1921	PIPE CULVERTS, CLASS A, TYPE 3 36"	FOOT	40.0	40.0							
542A1933	PIPE CULVERTS, CLASS A, TYPE 3 48"	FOOT	15.0	15.0							
542A1957	PIPE CULVERTS, CLASS A, TYPE 3 72"	FOOT	12.0	12.0							
542A2755	PIPE CULVERTS, CLASS A, TYPE 4 30"	FOOT	60.0	60.0							
542A2773	PIPE CULVERTS, CLASS A, TYPE 4 48"	FOOT	25.0	25.0							
542A3427	PIPE CULVERTS, CLASS A, TYPE 5 72"	FOOT	30.0	30.0							
54207153	PIPE CULVERTS, TYPE 1, REINFORCED CONCRETE - ELLIPTICAL, EQUIVALENT ROUND-SIZE 18"	FOOT	157.0								157.0
54207162	PIPE CULVERTS, TYPE 1, REINFORCED CONCRETE - ELLIPTICAL, EQUIVALENT ROUND-SIZE 27"	FOOT	26.0								26.0
54207195	PIPE CULVERTS, TYPE 1, REINFORCED CONCRETE - ELLIPTICAL, EQUIVALENT ROUND-SIZE 60"	FOOT	200.0								200.0
54213443	END SECTIONS 8"	EACH	82.0	82.0							
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	4.0	1.0							3.0
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	1.0								1.0
54213666	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 21"	EACH	6.0								6.0
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	5.0	5.0							
54214713	PRECAST REINFORCED CONCRETE FLARED END SECTIONS - ELLIPTICAL, EQUIVALENT ROUND-SIZE 18"	EACH	1.0								1.0
54214722	PRECAST REINFORCED CONCRETE FLARED END SECTIONS - ELLIPTICAL, EQUIVALENT ROUND-SIZE 27"	EACH	1.0								1.0
54214755	PRECAST REINFORCED CONCRETE FLARED END SECTIONS - ELLIPTICAL, EQUIVALENT ROUND-SIZE 60"	EACH	1.0								1.0

PLOT DATE = 12/14/2006
 FILE NAME = c:\p\projects\98950\add13\add13.tbl\sheet32
 USER = jck
 SCALE = 1/4" = 1'

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

6 OF 12

SCALE: VERT. DATE
 HORIZ. DRAWN BY JCK
 CHECKED BY