CONTRACT NO. 98950

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	26
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* FAI 57 & FAU 9629 (OLD IL 13)
** (X1-6-2)VB-2, (X1-6)HBK-2

STORM SEWERS

LOCATION	STORM SEWERS, CLASS A, TYPE 1								STORM SEWERS, CLASS A, TYPE 2			PRC FLARED END SECTIONS				TRENCH BACKFILL	CONCRETE COLLAR	REINFORCED CONCRETE PIPE ELBOW 24"	REINFORCED CONCRETE PIPE TEE 12" W/12" RISER	CONCRETE THRUST BLOCKS
	12"	15"	18"	21"	24"	27"	36"	42"	12"	21"	24"	12"	18"	21"	24"					
	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	EACH	EACH	EACH	EACH	CU YD	CU YD	EACH	EACH	EACH
FAI 57																				
STAGE 4	0	0	0	0	36	0	0	0	35	0	26	1	0	0	1	70	1.12	2	0	1
STAGE 5	429	0	0	0	0	0	0	0	0	0	0	0	0	0	0	206	0	0	1	0
STAGE 6	469	0	0	0	0	0	0	0	0	0	0	0	0	0	0	169	0	0	0	0
STAGE 7	366	391	513	258	0	0	0	0	0	0	0	0	0	0	0	907	0	0	0	0
STAGE 7C	172	172	244	22	0	0	0	0	0	0	0	0	0	0	0	302	0.5	0	0	0
FAI 57 PROJECT TOTALS	1436	563	757	280	36	0	0	0	35	0	26	1	0	0	1	1,654.0	1.6	2	1	1
FAU 9629 (OLD IL 13)																				
RT STA 761+53 TO STA 761+85						31														
RT STA 762+10														2						
RT STA 764+61													1							
RT STA 764+61 TO STA 764+90			24																	
RT STA 764+90 TO STA 765+35			42													9.2				
RT STA 765+35 TO STA 765+50	24															4.0				
RT STA 765+50												1								
RT STA 765+35 TO STA 766+02	64															18.3				
RT STA 767+68 TO STA 768+21	53															12.7				
RT STA 768+21 TO STA 768+77	50																			
RT STA 768+77												1								
RT STA 771+65												1								
RT STA 771+65 TO STA 771+72	5																			
LT STA 773+75 TO STA 773+85.5	5																			
RT STA 773+75 TO STA 774+10.						29		29								21.8				
RT STA 773+77.5	11															10.3				
LT STA 773+85.5																4.0				
RT STA 774+10 TO STA 774+48.						33		33								22.9				
RT STA 774+48 TO STA 774+53			17													6.6				
RT STA 774+48 TO STA 775+10	58															22.6				
RT STA 774+48 TO STA 775+60							108									79.6				

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

SCALE: VERT. HORIZ.
DATE
DRAWN BY JCK
CHECKED BY

PLOT DATE = 1/18/2007
FILE NAME = c:\pwworking\d02\d0230021\sdi3\sdi3sch.h32
PLOT SCALE = 50.0000 ' / IN.
USER NAME = krenzje