CONTRACT NO. 98950

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	34
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* FAI 57 & FAU 9629 (OLD IL 13)
** (X1-6-2)VB-2, (X1-6)HBK-2

DRAINAGE REMOVAL

LOCATION STATION	PAVED DITCH REMOVAL	CONCRETE HEADWALL REMOVAL		PIPE CULVERT REMOVAL			REMOVING INLETS	FILLING MANHOLES	STORM SEWER REMOVAL						TRENCH BACKFILL	CONCRETE REMOVAL	CLASS B PATCHES, TYPE IV, 10 INCH
		INFO. ONLY		INFORMATION ONLY					12"	15"	18"	24"	30"	48"			
	FOOT	REMOVAL (CU YDS)	EACH	CULVERT SIZE (INCH)	CULVERT TYPE	FOOT	EACH	EACH	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	CU YD	CU YD	SQ YD
FAU 9629 (OLD IL 13)																	
LT. STA. 755+15 TO STA. 755+31				18	RCCP	16											
RT. STA. 758+80	4																
RT. STA. 762+68 TO STA. 763+09				15	CPP	41									5.0		
RT. STA. 771+00 TO STA. 771+63	63																
STA. 771+47															113.0	7.0	54.0
RT. STA. 771+63		2.6	1														
RT. STA. 771+63 TO STA. 772+97														134	272.0		
LT. STA. 772+80							1										
LT. STA. 772+80 TO STA. 772+95									20						19.0		
STA. 773+00				60	RCCP	80									200.0		69.0
LT. STA. 773+00		5.4	1														
RT. STA. 773+00								1									
LT. STA. 773+07		0.8	1														
LT. STA. 773+09 TO STA. 773+51				18	RCCP	24									8.0		
LT. STA. 773+51		0.7	1														
RT. STA. 773+61 TO STA. 774+48													110		67.0		
LT. STA. 774+17		0.3	1				1		13								
RT. STA. 774+48							1										
RT. STA. 775+05								1									
RT. STA. 775+14								1									
RT. STA. 775+22							1										
RT. STA. 775+22 TO STA. 775+61													39		18.0		
RT. STA. 775+26 TO STA. 775+62												45			11.0		
RT. STA. 775+61							2			12					2.0		
RT. STA. 775+61 TO STA. 775+94												35			13.0		
RT. STA. 775+61 TO STA. 777+26													165		115.0		
RT. STA. 777+69							1										
RT. STA. 777+69 TO STA. 777+97												28			20.0		
RT. STA. 777+85 TO STA. 778+00												15			12.0		
RT. STA. 778+00							2					9			16.0		
RT. STA. 778+00 TO STA. 779+98												198			98.0		
RT. STA. 779+98							1										
RT. STA. 779+98 TO STA. 781+54												156			70.0		
RT. STA. 781+54							1										
RT. STA. 782+25							1										
RT. STA. 782+25 TO STA. 783+96											171				53.0		
RT. STA. 783+96							1										
FAU 9629 (OLD IL 13) PROJECT TOTALS	**67**		**5**			**161**	**13**	**3**	**33**	**12**	**171**	**486**	**314**	**134**	**1112**	**7**	**123**
SCHEDULE PROJECT SUB-TOTALS	**139**		**17**			**447**	**20**	**3**	**33**	**12**	**171**	**538**	**314**	**134**	**1,112**	**10**	**123**
FROM STORM SEWER SCHEDULE															**2,088**		
FROM BOX CULVERT SCHEDULE															**163**		
FROM PIPE CULVERT SCHEDULE															**144**		
PROJECT TOTALS	**139**		**17**			**447**	**20**	**3**	**33**	**12**	**171**	**538**	**314**	**134**	**3,507**	**10**	**123**

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

SCALE: VERT. HORIZ.

DATE

DRAWN BY JCK

CHECKED BY

PLOT DATE = 1/18/2007
FILE NAME = c:\projects\d902082\old13sch.m32
PLOT SCALE = 50.0000 ' / IN.
USER NAME = kramvajc