CONTRACT NO. 98950

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	35
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* FAI 57 & FAU 9629 (OLD IL 13)
** (X1-6-2)VB-2, (X1-6)HBK-2

CONCRETE CURB & GUTTER

LOCATION STA TO STA	COMBINATION CONCRETE CURB AND GUTTER, TYPE B - 6.06 FOOT	COMBINATION CONCRETE CURB AND GUTTER, TYPE B - 6.24 FOOT	CONCRETE MEDIAN SURFACE 4 INCH SQ FT	CONCRETE MEDIAN (SPECIAL) SQ FT	CORRUGATED MEDIAN SQ FT	PROTECTIVE COAT SQ YD	SUB-BASE GRANULAR MATERIAL, TYPE A 6" SQ YD	TOPSOIL FURNISH AND PLACE, 18" SQ YD
FAI 57								
STAGE 5	56.0	0.0	0.0	0.0	0.0	25.0	0.0	0.0
STAGE 6	255.0	1,060.0	4,118.0	0.0	0.0	743.0	0.0	0.0
FAI 57 PROJECT TOTALS	311.0	1,060.0	4,118.0	0.0	0.0	768.0	0.0	0.0
FAU 9629 (OLD IL 13)								
LT. STA. 754+65					34.0	4.0		
STA. 761+26.9 TO STA. 761+47.4				106.0		12.0	12.0	
STA. 762+62 TO STA. 769+13.3		666.0				222.0		
STA. 762+62 TO STA. 771+56		894.0				298.0		
STA. 762+62 TO STA. 763+00			375.0			42.0		
STA. 763+00 TO STA. 765+75								392.0
RT. STA. 764+82 TO STA. 768+30		349.0				116.0		
STA. 765+75 TO STA. 771+56			3,724.0			414.0		
STA. 769+13.3 TO STA. 771+56	245.0					41.0		
RT. STA. 771+56 TO RT. STA. 0+80 NEW ST.		57.0				19.0		
STA. 773+08 TO STA. 774+66				467.0		52.0		
LT. STA. 0+80 NEW ST. TO RT. STA. 774+72		233.0				78.0		
LT. STA. 773+69 TO STA. 774+68		97.0				32.0	39.0	
RT. STA. 775+08 TO STA. 777+31		251.0				84.0		
RT. STA. 777+65.3 TO STA. 781+80		432.0				144.0		
RT. STA. 782+03 TO STA. 784+05.3		214.0				71.0		
STA. 0+51 TO STA. 0+80 NEW ST.				160.0		18.0		
FAU 9629 (OLD IL 13) PROJECT TOTALS	245.0	3,193.0	4,099.0	733.0	34.0	1,647.0	51.0	392.0
SCHEDULE PROJECT SUB-TOTALS	556.0	4,253.0	8,217.0	733.0	34.0	2,415.0	51.0	392.0
FROM CONCRETE PAVEMENT SCHEDULE						7,898.0	463.0	
FROM CONCRETE BARRIER SCHEDULE						3,803.0		
FROM SIDEWALK SCHEDULE						1,188.0		
PROJECT TOTALS	556.0	4,253.0	8,217.0	733.0	34.0	15,304.0	514.0	392.0

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

SCALE: VERT. HORIZ.
DATE

DRAWN BY JCK
CHECKED BY

PLOT DATE = 1/16/2007
FILE NAME = c:\projects\d9629802\vol13\vol13sch.dgn
PLOT SCALE = 50.0000 ' / in.
USER NAME = kranzjo