CONTRACT NO. 98950

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	37
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* FAI 57 & FAU 9629 (OLD IL 13)
** (X1-6-2)VB-2, (X1-6)HBK-2

ENTRANCE AND SIDE ROAD

LOCATION STATION TO STATION		EXISTING ENTRANCE INFORMATION		INCIDENTAL BITUMINOUS SURFACING	BITUMINOUS MATERIALS (PRIME COAT)	AGGERGATE (PRIME COAT)	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	AGGREGATE BASE COURSE, TYPE A 4"	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	PCC SURFACE REMOVAL - BUTT JOINT	TEMPORARY RAMP
		TYPE	SURFACE	TON	GALLON	TON	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD
FAU 9629 (OLD IL 13)											
LT STA 754+63	COMFORT DR.	S.R.R	CONCRETE	43.0	46.0	0.8				147.0	68.0
RT STA 755+00		C.E.R.	CONCRETE	4.0	7.0						
RT STA 774+92	COMMANDER DR.	S.R.R	BITUMINOUS	29.0	31.0	0.5			52.0		20.0
LT STA 774+96	7TH STREET	S.R.R	CONCRETE	8.0	8.0	0.1				40.0	23.0
LT STA 776+42		C.E.R.	CONCRETE	1.0	2.0						
LT STA 777+01		C.E.R.	CONCRETE	1.0	1.0						
LT STA 778+27		C.E.R.	CONCRETE	1.0	1.0						
LT STA 778+82		C.E.R.	CONCRETE	1.0	2.0						
LT STA 780+28		C.E.R.	CONCRETE	1.0	2.0						
LT STA 780+98		C.E.R.	CONCRETE	1.0	2.0						
LT STA 782+14		C.E.R.	CONCRETE	1.0	1.0						
LT STA 782+93		C.E.R.	CONCRETE	1.0	2.0						
LT STA 784+61	5TH STREET	S.R.R	BITUMINOUS	7.0	7.0	0.1			81.0		17.0
CRISP DRIVE											
STA 10+80 TO STA 12+94.5		P.E.R.	BITUMINOUS	45.0	126.0			392.0			
NEW CITY STREET											
STA 00+30 TO STA 00+80		S.R.R.	CONCRETE				762.0				
FAU 9629 (OLD IL 13) PROJECT TOTAL				144.0	238.0	1.5	762.0	392.0	133.0	187.0	128.0
SCHEDULE PROJECT SUB-TOTAL				144.0	238.0	1.5	762.0	392.0	133.0	187.0	128.0
FROM BITUMINOUS PAVEMENT SCHEDULE					26,561.0	79.0					
FROM SHOULDER SCHEDULE					4,195.0						
FROM SURFACE REMOVAL SCHEDULE									3,281.0		1,458.0
PROJECT TOTAL				144.0	30,994.0	80.5	762.0	392.0	3,414.0	187.0	1,586.0

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

SCALE: VERT. HORIZ.
DATE

DRAWN BY JCK
CHECKED BY

PLOT DATE = 1/18/2007
FILE NAME = c:\pw_pw1\pw02802*.dgn
PLOT SCALE = 50.0000 ' / IN.
USER NAME = krenzje