

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	38
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

- * FAI 57 & FAU 9629 (OLD IL 13)
- ** (X1-6-2)VB-2, (X1-6)HBK-2

LIME MODIFIED SOILS

LOCATION STA TO STA	PROCESSING MODIFIED SOILS 12"	LIME	FOR INFO. ONLY WATER
	SQ YD	TON	UNIT
FAI 57			
STAGE 3	847.0	25.0	13.0
STAGE 5	7,208.0	12.0	24.0
STAGE 6	9,079.0	31.0	15.0
FAI 57 PROJECT TOTALS	17,134.0	68.0	52.0
FAU 9629 (OLD IL 13)			
RT STA. 757+15 TO STA. 759+89	496.0	15.0	7.0
RT STA. 759+89 TO STA. 764+82	1,108.0	33.0	17.0
RT STA. 764+82 TO STA. 766+00	250.0	7.0	4.0
RT STA. 766+00 TO STA. 767+66	260.0	8.0	4.0
RT STA. 767+66 TO STA. 768+30	115.0	3.0	2.0
RT STA. 768+30 TO STA. 768+61	74.0	2.0	1.0
RT STA. 768+61 TO STA. 769+60	267.0	8.0	4.0
RT STA. 769+60 TO STA. 771+53	583.0	17.0	9.0
RT STA. 771+53 TO STA. 773+80	283.0	8.0	4.0
RT STA. 773+80 TO STA. 774+24	69.0	2.0	1.0
RT STA. 774+24 TO STA. 775+55	163.0	5.0	2.0
RT STA. 775+55 TO STA. 776+31	119.0	4.0	2.0
RT STA. 776+31 TO STA. 777+10	133.0	4.0	2.0
RT STA. 777+10 TO STA. 779+55	438.0	13.0	7.0
RT STA. 779+55 TO STA. 783+55.5	472.0	14.0	7.0
RT STA. 783+55.5 TO STA. 784+40	39.0	1.0	1.0
FAU 9629 (OLD IL 13) PROJECT TOTAL	4,869.0	144.0	74.0
PROJECT TOTALS	22,003.0	212.0	126.0

PLOT DATE = 11/05/2006
 PLOT SCALE = 50.0000 / IN.
 USER NAME = krenz,jp

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

SCALE: VERT.
HORIZ.
DATE

DRAWN BY JCK
CHECKED BY