CONTRACT NO. 98950

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	39
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* FAI 57 & FAU 9629 (OLD IL 13)
** (X1-6-2)VB-2, (X1-6)HBK-2

EARTHWORK

LOCATION STA TO STA	EARTH EXCAVATION	FOR INFORMATION ONLY: AVERAGE SHRINKAGE FACTOR	EARTH EXCAVATION (ADJUSTED)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) SHORTAGE (-)	BORROW SWELL FACTOR	BORROW EXCAVATION	REMARKS
	CU YD	%	CU YD	CU YD	CU YD	%	CU YD	
FAI 57								
STAGE 1	1,066	27.0%	771	5,982	-5,211	25.0%	6,514	
STAGE 1A	5,597	11.7%	5,290	4,088	-3,074	25.0%	3,843	
STAGE 2	471	16.8%	387	483	-96	25.0%	120	
STAGE 3	12,420	21.1%	9,530	13,885	-85	25.0%	106	
STAGE 4	1,808	15.9%	1,514	42,784	-41,270	25.0%	51,588	
STAGE 5	4,005	18.1%	3,337	24,902	-21,565	25.0%	26,956	
STAGE 6	19,219	22.0%	14,936	23,213	-8,277	25.0%	10,346	
STAGE 7	1,465	26.5%	928	3,100	-2,172	25.0%	2,715	
STAGE 7A	0	36.8%	0	80	-80	25.0%	100	
STAGE 7C	27	35.4%	18	220	-202	25.0%	253	
STAGE 8	2,554	30.5%	1,774	1,220	554	0.0%	0	
FAI 57 PROJECT TOTAL	48,632						102,541	
FAU 9629 (OLD IL 13)								
STA 755+00 TO STA 784+25	5,527	30.3%	3,850	929	2,921	0%	0	
CRISP DRIVE								
STA 10+78 TO STA 12+94	162	36.8%	102	7	95	0%	0	
FAU 9629 (OLD IL 13) PROJECT TOTAL	5,689						0	
PROJECT TOTAL	54,321						102,541	

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

SCALE: VERT. HORIZ.
DATE

DRAWN BY JCK
CHECKED BY

PLOT DATE = 1/16/2007
FILE NAME = c:\pw\projects\r982082\old13sch.m52
PLOT SCALE = 50.0000 / IN.
USER NAME = kranzjo