

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	45
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

- FAI 57 & FAU 9629 (OLD IL 13)
- ** (X1-6-2)VB-2, (X1-6)HBK-2

EROSION CONTROL

LOCATION STATION TO STATION	PIPE CULVERT (EROSION CONTROL)	EROSION CONTROL BLANKET	HEAVY DUTY EXCELSIOR BLANKET	PERIMETER EROSION BARRIER	EARTH EXCAVATION FOR EROSION CONTROL	AGGREGATE (EROSION CONTROL)	TEMPORARY DITCH CHECKS	INLET & PIPE PROTECTION	END SECTIONS 8"	REMARKS
	FOOT	SQ YD	SQ YD	FOOT	CU YD	TON	EACH	EACH	EACH	
FAI 57										
STAGE 1	255.0	5,801.0	0.0	1,878.0	0.0	20.0	0.0	0.0	10.0	
STAGE 1A	0.0	0.0	0.0	0.0	0.0	0.0	7.0	3.0	0.0	
STAGE 3	173.0	13,630.0	0.0	1,446.0	22.0	18.0	19.0	3.0	8.0	
STAGE 4	606.0	19,300.0	0.0	6,078.0	11.0	55.0	0.0	0.0	27.0	
STAGE 5	335.0	5,888.0	462.0	2,863.0	0.0	32.0	15.0	4.0	16.0	
STAGE 6	343.0	6,060.0	1,435.0	4,370.0	0.0	42.0	24.0	4.0	21.0	
STAGE 7C	0.0	244.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
STAGE 8	0.0	5,515.0	1,032.0	0.0	0.0	0.0	22.0	0.0	0.0	
FAI 57 PROJECT TOTALS	1,712.0	56,438.0	2,929.0	16,635.0	33.0	167.0	87.0	14.0	82.0	
FAU 9629 (OLD IL 13)										
LT STA 755+18 TO STA 761+35		1,590.0								
LT STA 756+25								1.0		
LT STA 756+75								1.0		
LT STA 757+25					6.0	0.6				
LT STA 758+00							1.0			
LT STA 759+00							1.0			
LT STA 760+00							1.0			
LT STA 761+00							1.0			
LT STA 763+00 TO STA 766+05		646.0								
LT STA 763+50							1.0			
LT STA 765+50							1.0			
RT STA 757+25 TO STA 761+97		2,005.0								
RT STA 757+25							1.0			
RT STA 757+50					6.0	0.6				
RT STA 758+50							1.0			
RT STA 758+80								1.0		
RT STA 759+75							1.0			
RT STA 761+00							1.0			
RT STA 761+85								1.0		

1 OF 2

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
SCALE: VERT.	DRAWN BY JCK	CHECKED BY
HORIZ.		
DATE		