CONTRACT NO. 98950

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	47
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* FAI 57 & FAU 9629 (OLD IL 13)
** (X1-6-2)VB-2, (X1-6)HBK-2

SEEDING

LOCATION STATION TO STATION	TEMPORARY EROSION CONTROL SEEDING	SEEDING, CLASS 1B	SEEDING, CLASS 7	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	AGRICULTURAL GROUND LIMESTONE	MULCH, METHOD 2
	POUND	ACRE	ACRE	POUND	POUND	POUND	TON	ACRE
FAI 57								
STAGE 1	130.0	1.29	1.30	208.0	155.0	155.0	2.6	2.59
STAGE 1A	105.0	1.05	1.05	169.0	126.0	126.0	2.1	2.10
STAGE 2	2.0	0.00	0.08	3.4	0.0	0.0	0.0	0.08
STAGE 3	495.0	3.94	4.95	670.0	473.0	473.0	7.9	8.89
STAGE 4	520.0	3.75	5.20	657.0	450.0	450.0	7.5	8.95
STAGE 5	289.0	2.81	2.89	459.0	338.0	338.0	5.7	5.70
STAGE 6	544.0	4.83	5.44	846.0	580.0	580.0	9.7	10.27
STAGE 7C	5.0	0.05	0.05	8.0	6.0	6.0	0.1	0.10
STAGE 8	280.0	3.94	2.80	493.0	473.0	473.0	7.9	6.74
FAI 57 PROJECT TOTALS	**2,370.0**	**21.66**	**23.76**	**3,513.4**	**2,601.0**	**2,601.0**	**43.5**	**45.42**
FAU 9629 (OLD IL 13)								
LT STA 755+18 TO STA 761+35	32.8	0.3	0.3	52.6	39.4	39.4	0.7	
LT STA 763+00 TO STA 766+05	13.3	0.1	0.1	21.3	16.0	16.0	0.3	
RT STA 757+25 TO STA 761+97	41.4	0.4	0.4	66.3	49.7	49.7	0.8	
RT STA 762+23 TO STA 766+08	25.1	0.3	0.3	40.1	30.1	30.1	0.5	
RT STA 767+63 TO STA 771+95	26.1	0.3	0.3	41.7	31.3	31.3	0.5	
RT STA 771+65 TO STA 772+80	4.3	0.1	0.1	6.9	5.2	5.2	0.1	
RT STA 772+70 TO STA 774+67	9.6	0.1	0.1	15.3	11.5	11.5	0.2	
RT STA 775+07 TO STA 777+27	5.7	0.1	0.1	9.1	6.8	6.8	0.1	
RT STA 777+66 TO STA 781+80	13.2	0.1	0.1	21.1	15.8	15.8	0.3	
RT STA 782+05 TO STA 784+05	4.6	0.1	0.1	7.3	5.5	5.5	0.1	
CRISP DRIVE								
STA 10+80 TO STA 13+00	17.7	0.2	0.2	28.3	21.2	21.2	0.4	
FAU 9629 (OLD IL 13) PROJECT TOTALS	**193.8**	**2.10**	**2.10**	**310.0**	**232.5**	**232.5**	**4.0**	**0.00**
PROJECT TOTALS	**2,563.8**	**23.76**	**25.86**	**3,823.4**	**2,833.5**	**2,833.5**	**47.5**	**45.42**

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

SCALE: VERT. HORIZ.
DATE
DRAWN BY JCK
CHECKED BY

PLOT DATE = 1/17/2007
FILE NAME = c:\pw_work\pw02002\old13\old13sch.h32
PLOT SCALE = 50.0000 / IN.
USER NAME = kramzajo