CONTRACT NO. 98950

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	50
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* FAI 57 & FAU 9629 (OLD IL 13)
** (X1-6-2)VB-2, (X1-6)HBK-2

PERMANENT PAVEMENT MARKINGS

LOCATION STATION TO STATION	THERMOPLASTIC PAVEMENT MARKING									PREFORMED PLASTIC PAVEMENT MARKING				
	LINE 4"			LINE 6"	LINE 8"	LINE 12"		LINE 24"	LETTERS AND SYMBOLS	TYPE B - LINE 4"			TY B - LINE 8"	TY B - LINE 12"
	SOLID WHITE	SKIP-DASH YELLOW	SOLID YELLOW	SOLID WHITE	SOLID WHITE	SOLID WHITE	SOLID YELLOW	SOLID WHITE		WHITE	YELLOW	WHT. SKIP-DASH	WHITE	WHITE
	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT	FOOT	FOOT	FOOT	FOOT	FOOT
FAI 57														
NORTHBOUND														
STA. 1506+90 TO STA. 1512+12														283
STA. 1506+90 TO STA. 1509+63										78	273	70		
STA. 1509+63 TO STA. 1510+48.26 BK										171	85	20		
STA. 1510+49.48 AH TO STA. 1511+69										242	120	30		
STA. 1511+69 TO STA. 1516+69										85	500	130		
STA. 1512+55 TO STA. 1516+62												100		
STA. 1516+69 TO STA. 1528+26										2078	1157	290		
STA. 1528+26 TO STA. 1534+86											660	170	360	
STA. 1534+86 TO STA. 1543+00										814	814	200		
SOUTHBOUND														
STA. 1500+00 TO STA. 1503+05										305	305	80		
STA. 1503+05 TO STA. 1508+10 ENTERING FROM RAMP C											505	130	505	
STA. 1508+10 TO STA. 1509+43.50 BK											134	60		
STA. 1509+15.58 AH TO STA. 1519+39										624	1,023	360		
STA. 1513+09 TO STA. 1519+39 EXITING RAMP F													630	
STA. 1515+57 TO STA. 1523+50														277
STA. 1519+39 TO STA. 1529+50										1182	1011	250		
STA. 1529+50 TO STA. 1555+97											2647	660		
RAMP E														
STA. 3+48 TO STA. 13+27	979		979											
STA. 13+27 TO STA. 15+66					239					239			239	
STA. 15+60 TO STA. 20+18										452				
RAMP EE														
STA. 0+00 TO STA. 6+60										660				
STA. 3+00 TO STA. 6+60													360	
STA. 6+60 TO STA. 16+70	1,010		1,010											
RAMP F														
STA. 0+00 TO STA. 4+54										454				
STA. 4+54 TO STA. 12+62	808		808											
STA. 0+71 TO STA. 4+55													384	
RAMP FF														
STA. 3+37.79 TO STA. 8+36	498		498											
STA. 8+36 TO STA. 10+65													229	
STA. 8+36 TO STA. 37+16.72										2,881				
STA. 10+65 TO STA. 26+50												400		
RAMP C (SB I-57 STATIONING)														
STA. 1502+10 TO STA. 1505+27	326													
STA. 1502+80 TO STA. 1503+05			25											
STA. 1505+27 TO STA. 1507+08	181													
STA. 1503+05 TO STA. 1504+90					185									
RAMP B														
STA. 0+00 TO STA. 2+73										468				
FAI 57 PROJECT SUB-TOTALS	3,802	0	3,320			0	0			10,733	9,234	2,950		
FAI 57 PROJECT TOTALS		7,122		0	424	0		0	0		22,917		2,707	560

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

SCALE: VERT. HORIZ.
DATE
DRAWN BY JCK
CHECKED BY

PLOT DATE = 12/11/2006
FILE NAME = c:\projects\d902892\old13\old13sch=32
PLOT SCALE = 50.0000 ' / IN.
USER NAME = k-renz,je