CONTRACT NO. 98950

F.A. RTE. *	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	53
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* FAI 57 & FAU 9629 (OLD IL 13)
** (X1-6-2)VB-2, (X1-6)HBK-2

POLYUREA PAVEMENT MARKINGS

LOCATION STATION TO STATION	POLYUREA PAVEMENT MARKING TYPE II - LINE 4" SKIP-DASH WHITE FOOT	LINE 4" SOLID WHITE FOOT	LINE 4" SOLID YELLOW FOOT	LINE 6" SOLID WHITE FOOT	LINE 12" SOLID WHITE FOOT	LINE 24" SOLID WHITE FOOT	LETTERS AND SYMBOLS SQ FT
FAI 57							
NORTHBOUND							
STA 1515+63.11 TO STA 1517+56.11	50	193.00	193.00				
STA 1528+80.23 TO STA 1531+14.23	60	234.00	234.00				
SOUTHBOUND							
STA 1515+61.02 TO STA 1517+54.02	50	193.00	193.00				
STA 1528+78 TO STA 1531+12	60	234.00	234.00				
RAMP E							
STA. 0+68 STOP BAR						18	
STA. 0+34 TO STA. 0+88 PAINTED MEDIAN		170			63		
STA. 0+34 TO STA. 0+76		96					
STA. 0+76 TO STA. 3+46		274	275				
RAMP EE							
STA. 19+48 STOP BAR						12	
STA. 19+57 STOP BAR						13	
STA. 19+81 STOP BAR						18	
STA. 19+28 TO STA. 19+92 PAINTED MEDIAN					130		
STA. 17+58 ONLY (2 EA)							41.6
STA. 18+03 ONLY							20.8
STA. 17+86 TURN ARROW							15.6
STA. 18+31 TURN ARROW							15.6
STA. 17+86 THRU ARROW							11.5
STA. 16+69.69 TO STA. 17+48		80	78				
STA. 17+48 TO STA. 17+93		135	45				
STA. 17+93 TO STA. 19+60		281	157				
STA. 19+28 TO STA. 19+92		216					
STA. 17+93 TO STA. 19+92		324					
RAMP F							
STA. 13+60.5 ONLY							41.6
STA. 13+88.5 TURN ARROW							31.2
STA. 15+48 STOP BAR						19	
STA. 15+63 STOP BAR						18	
STA. 15+20 TO STA. 15+84 PAINTED MEDIAN					136		
STA. 12+62 TO STA. 13+40		168	78				
STA. 13+40 TO STA. 15+20		360	180				
STA. 15+20 TO STA. 15+49		96	29				
STA. 15+49 TO STA. 15+82		263	9				
RAMP FF							
STA. 0+34 TO STA. 2+00		218					
STA. 0+61 TO STA. 3+37.79			278				
STA. 2+00 TO STA. 3+37.79		138					
STA. 0+70 STOP BAR						18	
STA. 0+34 TO STA. 0+89 PAINTED MEDIAN		172			70		
FAI 57 PROJECT SUBTOTALS	220	3,845	1,983	0	399	116	178
FAI 57 PROJECT TOTALS		6,048		0	399	116	178
FAU 9629 (OLD IL 13)							
CRISP DR.							
STA. 10+47						15	
STA. 10+75				48			
FAU 9629 (OLD IL 13) PROJECT TOTALS	0	0	0	48	0	15	0
FAU 9629 (OLD IL 13) PROJECT TOTALS		0		48	0	15	0
PROJECT TOTALS		6,048		48	399	131	178

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

SCALE: VERT. HORIZ.

DATE

DRAWN BY JCK

CHECKED BY

PLOT DATE = 12/11/2006
FILE NAME = c:\projects\d982002\old13\old13schu32
PLOT SCALE = 50.0000 ' / IN.
USER NAME = kramage