CONTRACT NO. 98950

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	54
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* FAI 57 & FAU 9629 (OLD IL 13)
** (X1-6-2)VB-2, (X1-6)HBK-2

TEMPORARY PAVEMENT MARKINGS

LOCATION STATION TO STATION	PAVEMENT MARKING TAPE, TYPE I I I (SPECIAL) LINE 4" SKIP-DASH WHITE FOOT	PAVEMENT MARKING TAPE, TYPE I I I (SPECIAL) LINE 4" SOLID WHITE FOOT	PAVEMENT MARKING TAPE, TYPE I I I (SPECIAL) LINE 4" SOLID YELLOW FOOT	TEMPORARY PAINT PAVEMENT MARKING LINE 4" SKIP-DASH WHITE FOOT	TEMPORARY PAINT PAVEMENT MARKING LINE 4" SOLID WHITE FOOT	TEMPORARY PAINT PAVEMENT MARKING LINE 4" SKIP-DASH YELLOW FOOT	TEMPORARY PAINT PAVEMENT MARKING LINE 4" SOLID YELLOW FOOT	TEMPORARY PAINT PAVEMENT MARKING LINE 6" SOLID WHITE FOOT	TEMPORARY PAINT PAVEMENT MARKING LINE 8" SOLID WHITE FOOT	TEMPORARY PAINT PAVEMENT MARKING LINE 8" SOLID YELLOW FOOT	TEMPORARY PAINT PAVEMENT MARKING LINE 12" SOLID WHITE FOOT	TEMPORARY PAINT PAVEMENT MARKING LINE 12" SOLID YELLOW FOOT	TEMPORARY PAINT PAVEMENT MARKING LINE 24" SOLID WHITE FOOT	TEMPORARY PAINT PAVEMENT MARKING LETTERS AND SYMBOLS SQ FT	SHORT TERM PAVEMENT MARKING WHITE FOOT	SHORT TERM PAVEMENT MARKING YELLOW FOOT
FAI 57																
PRE-STAGE 1																
STA. 1489+62 TO STA. 1506+87 NORTHBOUND				0												1,725
STA. 1475+00 TO STA. 1492+15 SOUTHBOUND				0												1,715
PRE-STAGE 2																
STA 1504+03 TO STA 1506+87 NORTHBOUND				70											1,435	
STA 1475+03 TO STA 1477+85 SOUTHBOUND				70											1,435	
PRE-STAGE 3																
STA 1497+00 TO STA 1506+87 NORTHBOUND				250												
STA 1477+85 TO STA 1485+00 SOUTHBOUND				180												
STA 1514+14 TO STA 1530+76 SOUTHBOUND				0												1,662
PRE-STAGE 4																
STA 1514+14 TO STA 1519+00 SOUTHBOUND				120											325	
STA 1519+00 TO STA 1530+76.5 SOUTHBOUND				290											1,176	
STAGE 1A	0	0	0	2,088	6,096	0	8,145	0	0	90	0	0	0	0	0	0
STAGE 2	0	0	0	2,788	8,537	0	4,351	0	0	135	0	0	0	0	0	0
STAGE 3	0	0	0	0	185	0	0	0	0	0	0	0	0	0	0	0
STAGE 4	0	0	0	2,370	14,056	0	10,218	0	0	0	0	0	0	0	0	0
STAGE 5	0	0	0	0	675	0	311	0	79	0	0	0	0	0	0	0
STAGE 6	0	0	0	0	505	0	0	0	0	0	0	0	0	0	0	0
STAGE 7	110	747	614	1,700	14,192	0	10,088	0	0	0	0	0	0	0	0	0
STAGE 7B	243	2,775	861	2,226	8,622	0	8,439	0	1,749	0	0	0	0	0	0	0
STAGE 8	290	2,984	854	2,920	15,200	0	12,839	0	2,597	0	895	0	116	178	1,128	600
FAI 57 PROJECT SUBTOTALS	643	6,506	2,329	15,072	68,068	0	54,391	0	4,425	225	895	0	116	178	5,499	5,702
FAI 57 PROJECT TOTALS		9,478			137,531			0	4,650		895		116	178	11,201	

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

SCALE: VERT. HORIZ.
DATE
DRAWN BY JCK
CHECKED BY

PLOT DATE = 1/18/2007
FILE NAME = c:\pro_gests\d982882\old13sch\sh32
PLOT SCALE = 50.0000 ' / IN.
USER NAME = krenzje