

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	64

STA.	TO STA.
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT

- FAI 57 & FAU 9629 (OLD IL 13)
- ** (X1-6-2IVB-2, (X1-6)HBK-2

SIGNS

LOCATION STATION TO STATION	OFFSET FROM EDGE OF PAVEMENT TO FIRST POST	SIGN ID NO.	SIGN PANEL - TYPE 1	SIGN PANEL - TYPE 3	CONCRETE FOUNDATIONS CU YD	DRILLED SHAFT CONCRETE FOUNDATIONS CU YD	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY		CONCRETE FOUNDATION, GROUND MOUNT CU YD	OVERHEAD SIGN STRUCTURE - SPAN, TYPE I-A (4' -0" X 4' -6")	OVERHEAD SIGN STRUCTURE - CANTILEVER, TYPE II-C-A (36" X 5' -6")	OVERHEAD SIGN WALKWAY, TYPE A FOOT	OVERHEAD SIGN WALKWAY, CANTILEVER, TYPE A FOOT	REMARKS
			SQ FT	SQ FT			POST SIZE (INFO. ONLY)	POUND		FOOT	FOOT			
FAI 57														
NORTHBOUND														
STA 1532+00		9S1001057L52.8		174.0	17.2	14.8				80.0		57.0		FOUNDATION IN MEDIAN MUST BE DONE IN I-57 STAGE 7
STA 1532+00				217.5										SIGN PANEL-TYPE 3 IS PAID 100% STATE
STA 1532+00				117.0										SIGN PANEL-TYPE 3 IS PAID 100% STATE
STA 1532+00				72.0										SIGN PANEL-TYPE 3 IS PAID 100% STATE
LT STA 1535+00	36.7						W6 X 15	562.5	1.4					
LT STA 1545+50	32.5			131.3			W10 X 26	1,307.8	2.4					
SOUTHBOUND														
STA 1515+50		9C1001057R53.1		117.0		6.9					30.0		14.0	SIGN PANEL-TYPE 3 IS PAID 100% STATE
RAMP EE														
RT STA 11+50	22.0			47.5			W6 X 15	595.5	1.4					
RT STA 13+00	21.2			76.0			W8 X 18	822.6	1.4					
RT STA 14+50	18.5			100.0			W8 X 18	801.0	1.4					
RT STA 16+00	18.5			100.0			W8 X 18	765.0	1.4					
RT STA 17+50	18.2			110.0			W8 X 18	768.6	1.4					
RAMP F														
RT STA 8+00	21.5			47.5			W6 X 15	594.0	1.4					
RT STA 9+50	21.5			76.0			W6 X 15	610.5	1.4					
RT STA 11+50	24.2			100.0			W8 X 18	810.0	1.4					
RT STA 13+00	22.5			100.0			W8 X 18	756.0	1.4					
RT STA 14+40	31.0			110.0			W10 X 22	1,174.8	1.4					SIGN STRADDLES DITCH
FAI 57 PROJECT TOTALS			0	1695.8	17.2	21.7		9568.3	17.8	80	30	57	14	
FAU 9629 (OLD IL 13)														
RT STA 761+50	26.2			132.0			W8 X 18	788.4	1.4					
LT STA 763+25	27.2			63.0			W6 X 15	504.0	1.4					
RT STA 771+50	17.1			75.0			W6 X 15	585.0	1.4					SIGN STRADDLES DITCH
RT STA 771+77			9.0											
LT STA 772+67			9.0											
LT STA 773+50	18.9			155.3			W10 X 26	1,333.8	2.4					
FAU 9629 (OLD IL 13) PROJECT TOTALS			18	425.3	0	0		3211.2	6.6	0	0	0	0	
PROJECT TOTALS			18.0	2,121.1	17.2	21.7		12,779.5	24.4	80.0	30.0	57.0	14.0	

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCHEDULE
SCALE: VERT.	DRAWN BY JCK	DATE
HORIZ.	CHECKED BY	