CONTRACT NO. 98950

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	145
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* FAI 57 & FAU 9629 (OLD IL 13)
** (X1-6-2)VB-2, (X1-6)HBK-2

BITUMINOUS PAVEMENT - FAI 57 STAGE 1

LOCATION STATION TO STATION	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE SUPERPAVE MIX D, N105	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE SUPERPAVE MIX E, N105	POLYMERIZED BITUMINOUS CONCRETE BINDER COURSE SUPERPAVE IL-19.0, N105	BITUMINOUS CONCRETE BINDER COURSE SUPERPAVE IL-19.0, N90 INFO. ONLY		BITUMINOUS CONCRETE PAVEMENT (FULL DEPTH) SUPERPAVE, 14 1/4" FOR INFORMATION ONLY POLY BIT SURFACE MIX D, N105 1 1/2"	POLY BIT BINDER IL-19.0, N105 2 1/4"	BIT BINDER IL-19.0, N90 10 1/2"		STABILIZED SUB-BASE 4"	STABILIZED SUB-BASE (VARIABLE DEPTH)	SUB-BASE GRANULAR MATERIAL, 6"	SUB-BASE GRANULAR MATERIAL, 10"	SUB-BASE GRANULAR MATERIAL, TYPE C	BITUMINOUS MATERIAL (PRIME COAT)	AGGREGATE (PRIME COAT)	MATERIAL TRANSFER DEVICE
	TON	TON	TON	THICKNESS (IN.)	TON	TON	TON	TON	SQ YD	SQ YD	TON	SQ YD	SQ YD	TON	GALLON	TON	TON
FAI 57																	
NORTHBOUND																	
STA 1542+33 TO STA 1550+25			68	9.75	317.0										197		
STA 1542+33 TO STA 1551+75												680.0					
STA 1550+25 TO STA 1551+75			13	9.75	60.0										37		
SOUTHBOUND																	
STA 1500+00 TO STA 1504+00			67	9.75	301.0							555.0			181		
STA 1502+10 TO STA 1504+00			29	9.75	131.0							248.0		13	80		
STA 1504+00 TO STA 1510+00												947.0		43			
STA 1504+00 TO STA 1509+43.5 BK			93	9.75	420.0										254		
STA 1509+15.58 AH TO STA 1510+00			18	9.75	81.0										49		
STA 1507+18 TO STA 1509+43.5 BK			41	12.75	232.0										104		
STA 1509+15.58 AH TO STA 1510+00			13	12.75	73.0										33		
STA 1542+33 TO STA 1550+25			68	9.75	317.0										197		
STA 1542+33 TO STA 1556+85												1,049.0					
STA 1550+25 TO STA 1556+85			56	9.75	264.0										164		
FAI 57 STAGE 1 PROJECT TOTALS	0	0	466		2,196				0	0	0	3,479	0	56	1,296	0	0

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

SCALE: VERT. HORIZ.

DATE

DRAWN BY JCK

CHECKED BY

PLOT DATE = 1/16/2007
FILE NAME = c:\pwworking\d02\d0292802\sheet\sch_m32
PLOT SCALE = 50.0000 ' / IN.
USER NAME = krenzje