

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	151

STA.	TO STA.
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT

- \* FAI 57 & FAU 9629 (OLD IL 13)
- \*\* (X1-6-2)VB-2, (X1-6)HBK-2

### EROSION CONTROL - FAI 57 STAGE 1

LOCATION STATION TO STATION	PIPE CULVERT (EROSION CONTROL)	EROSION CONTROL BLANKET	HEAVY DUTY EXCELSIOR BLANKET	PERIMETER EROSION BARRIER	EARTH EXCAVATION FOR EROSION CONTROL	AGGREGATE (EROSION CONTROL)	TEMPORARY DITCH CHECKS	INLET & PIPE PROTECTION	END SECTIONS 8"	REMARKS
	FOOT	SQ YD	SQ YD	FOOT	CU YD	TON	EACH	EACH	EACH	
<b>FAI 57</b>										
<b>SOUTHBOUND</b>										
RT STA 1500+00 TO STA 1503+00		391.0								
RT STA 1502+14 TO STA 1510+00		5,410.0		836.0						APPROXIMATE OFFSET =100'
RT STA 1503+60 TO STA 1510+00				677.0						APPROXIMATE OFFSET =80'
RT STA 1504+08	31.0					2.0			1.0	
RT STA 1504+12	10.0					2.0			1.0	
RT STA 1505+00 TO STA 1508+70				365.0						APPROXIMATE OFFSET =65'
RT STA 1506+09	50.0					2.0			1.0	
RT STA 1506+12	29.0					2.0			1.0	
RT STA 1506+16	9.0					2.0			1.0	
RT STA 1507+70	50.0					2.0			1.0	
RT STA 1507+73	29.0					2.0			1.0	
RT STA 1507+76	8.0					2.0			1.0	
RT STA 1509+17	29.0					2.0			1.0	
RT STA 1509+20	10.0					2.0			1.0	
<b>FAI 57 STAGE 1 PROJECT TOTAL</b>	<b>255.0</b>	<b>5,801.0</b>	<b>0.0</b>	<b>1,878.0</b>	<b>0.0</b>	<b>20.0</b>	<b>0.0</b>	<b>0.0</b>	<b>10.0</b>	

PLOT DATE = 11/9/2006  
 PLOT SCALE = 50.0000' / IN.  
 USER NAME = kranz,jp

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION	
NAME	DATE	<b>SCHEDULE</b>	

SCALE: VERT. \_\_\_\_\_  
 HORIZ. \_\_\_\_\_  
 DATE \_\_\_\_\_  
 DRAWN BY JCK  
 CHECKED BY \_\_\_\_\_