CONTRACT NO. 98950

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	153
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* FAI 57 & FAU 9629 (OLD IL 13)
** (X1-6-2)VB-2, (X1-6)HBK-2

GUARD RAIL - FAI 57 STAGE 1

LOCATION STATION TO STATION	CORING FOR GUARDRAIL INSTALLATION	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 1, (FLARED)	STEEL PLATE BEAM GUARD RAIL, TYPE A	TRAFFIC BARRIER TERMINAL, TYPE 2	TRAFFIC BARRIER TERMINAL, TYPE 5	TRAFFIC BARRIER TERMINAL, TYPE 6	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)	GUARDRAIL REMOVAL	TEMPORARY STEEL PLATE BEAM GUARDRAIL, TYPE A	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 5	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 6	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 10	REMARKS
	FOOT	EACH	FOOT	EACH	EACH	EACH	EACH	FOOT	FOOT	EACH	EACH	EACH	
FAI 57													
SOUTHBOUND													
RT (OUTSIDE SHOULDER)													
STA. 1501+89 TO STA. 1510+00							1	843.0	805.0				NOTE 1
FAI 57 STAGE 1 PROJECT TOTALS	0.0	0	0.0	0	0	0	1	843.0	805.0	0	0	0	

NOTE: 1.) THE FACE OF THE **TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)** SHALL BE PLACED NEXT TO THE SHOULDER IN THE 2 FT BITUMINOUS SHOULDER. THE FACE OF THE **TEMPORARY STEEL PLATE BEAM GUARDRAIL, TYPE A** SHALL BE PLACED NEXT TO THE 2 FT BITUMINOUS SHOULDER WITH A TAPER BETWEEN THEM SHOWN ON THE PLANS. SEE TYPICAL FOR MORE CLARIFICATION. THE **TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)** SHALL USE A FLARE RATE OF 15:1.

NOTE: 1.) THE FACE OF THE **TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)** SHALL BE PLACED NEXT TO THE SHOULDER IN THE 2 FT BITUMINOUS SHOULDER. THE FACE OF THE **TEMPORARY STEEL PLATE BEAM GUARDRAIL, TYPE A** SHALL BE PLACED NEXT TO THE 2 FT BITUMINOUS SHOULDER WITH A TAPER BETWEEN THEM SHOWN ON THE PLANS. SEE TYPICAL FOR MORE CLARIFICATION. THE **TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)** SHALL USE A FLARE RATE OF 15:1.

PLOT DATE = 12/5/2005
FILE NAME = c:\pw_work\pw92802\old13\ed13ehar32
PLOT SCALE = 50.0000 ' / IN.
USER NAME = kranzjo

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

SCALE: VERT. HORIZ.
DATE
DRAWN BY JCK
CHECKED BY