CONTRACT NO. 98950

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	170
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* FAI 57 & FAU 9629 (OLD IL 13)
** (X1-6-2)VB-2, (X1-6)HBK-2

TEMPORARY PAVEMENT MARKINGS - FAI 57 STAGE 1A

LOCATION STATION TO STATION	PAVEMENT MARKING TAPE, TYPE I I I (SPECIAL) LINE 4" SKIP-DASH WHITE	LINE 4" SOLID WHITE	LINE 4" SOLID YELLOW	TEMPORARY PAINT PAVEMENT MARKING LINE 4" SKIP-DASH WHITE	LINE 4" SOLID WHITE	LINE 4" SKIP-DASH YELLOW	LINE 4" SOLID YELLOW	LINE 6" SOLID WHITE	LINE 8" SOLID WHITE	LINE 8" SOLID YELLOW	LINE 12" SOLID WHITE	LINE 12" SOLID YELLOW	LINE 24" SOLID WHITE	LETTERS AND SYMBOLS	SHORT TERM PAVEMENT MARKING WHITE	SHORT TERM PAVEMENT MARKING YELLOW
	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT	FOOT	FOOT
FAI 57																
NORTHBOUND																
STA. 1506+05 TO STA. 1506+90 NOTE 3					85		85									
STA. 1506+90 TO STA. 1507+81				23			91									
STA. 1507+81 TO STA. 1510+48.26 BK				67	268		268									
STA. 1510+49.47 AH TO STA. 1510+95				12	46		46									
STA. 1510+95 TO STA. 1518+78				196			783									
STA. 1517+30 TO STA. 1518+78 ON RAMP E				37												
STA. 1518+78 TO STA. 1526+85				202	807		807									
STA. 1526+85 TO STA. 1530+71				97			386									
STA. 1530+71 TO STA. 1542+33				291	1,162		1162									
STA. 1542+33 TO STA. 1543+18 SEE NOTE 2					170		85									
SOUTHBOUND																
STA. 1499+15 TO STA. 1500+00 SEE NOTE 2					170		85									
STA. 1500+00 TO STA. 1504+00				100	400		400									
STA. 1503+10 TO STA. 1504+00 ON RAMP C SEE NOTE 1					90					90						
STA. 1504+00 TO STA. 1506+10.5 ON RAMP C				53	211											
STA. 1504+00 TO STA. 1506+10.5				53			211									
STA. 1506+10.5 TO STA. 1509+43.5 BK				84	333		333									
STA. 1509+15.58 AH TO STA. 1517+34				205	819		819									
STA. 1517+34 TO STA. 1519+37				51			203									
STA. 1519+37 TO STA. 1526+25				172	688		688									
STA. 1526+25 TO STA. 1527+90 ON RAMP FF				42												
STA. 1526+25 TO STA. 1535+56				233			931									
STA. 1535+56 TO STA. 1542+33				170	677		677									
STA. 1542+33 TO STA. 1543+18 SEE NOTE 2					170		85									
FAI 57 STAGE 1A PROJECT SUBTOTALS	0	0	0	2,088	6,096	0	8,145	0	0	90	0	0	0	0	0	0
FAI 57 STAGE 1A PROJECT TOTALS	0			16,329				0	90		0		0	0	0	

NOTE: 1.) THE LEFT SOLID YELLOW LINE IS 8" WIDE. THEREFORE 2 STRIPS OF 4" TAPE SHALL BE PLACED.
2.) THE CENTERLINE AND THE RT. EDGELINE ARE SOLID WHITE.
3.) THE CENTERLINE IS SOLID WHITE.

PLOT DATE = 1/16/2007
FILE NAME = c:\pw_pw1\jd02802\old13\old13sch.m32
PLOT SCALE = 50.0000 ' / IN.
USER NAME = kramzjo

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

SCALE: VERT. HORIZ.
DATE
DRAWN BY JCK
CHECKED BY