

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	189

STA.	TO STA.
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT

- * FAI 57 & FAU 9629 (OLD IL 13)
- ** CX1-6-21VB-2, CX1-61HBK-2

BITUMINOUS PAVEMENT - FAI 57 STAGE 2

LOCATION STATION TO STATION	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE SUPERPAVE MIX D, N105	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE SUPERPAVE MIX E, N105	POLYMERIZED BITUMINOUS CONCRETE BINDER COURSE SUPERPAVE IL-19.0, N105	BITUMINOUS CONCRETE BINDER COURSE SUPERPAVE IL-19.0, N90		BITUMINOUS CONCRETE PAVEMENT (FULL DEPTH) SUPERPAVE, 14 1/4"				STABILIZED SUB-BASE 4"	STABILIZED SUB-BASE (VARIABLE DEPTH)	SUB-BASE GRANULAR MATERIAL, 6"	SUB-BASE GRANULAR MATERIAL, 10"	SUB-BASE GRANULAR MATERIAL, TYPE C	BITUMINOUS MATERIAL (PRIME COAT)	AGGREGATE (PRIME COAT)	MATERIAL TRANSFER DEVICE								
				INFO. ONLY	THICKNESS (IN.)	FOR INFORMATION ONLY			SQ YD									SQ YD	TON	SQ YD	SQ YD	TON	GALLON	TON	TON
						POLY BIT SURFACE MIX D, N105 1 1/2"	POLY BIT BINDER IL-19.0, N105 2 1/4"	BIT BINDER IL-19.0, N90 10 1/2"																	
				TON	TON	TON	TON	TON																	
FAI 57																									
NORTHBOUND																									
STA 1512+10 TO STA 1513+25			23.0	12.75	130.0																				
STA 1512+10 TO STA 1515+56											557.0						58								
STA 1513+25 TO STA 1515+56			47.0	12.75	268.0												120								
STA 1523+45 TO STA 1525+86			168.0	9.75	731.0						1,332.0						430								
SOUTHBOUND																									
STA 1520+43 TO STA 1522+15			82.0	9.75	358.0						651.0						211								
FAI 57 STAGE 2 PROJECT TOTALS	0	0	320		1,487			0	0	0	2,540	0	0	0	819	0	0								

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

SCALE: VERT. _____
HORIZ. _____

DATE _____

DRAWN BY JCK
CHECKED BY _____

PLOT DATE = 10/28/2006
 FILE NAME = c:\p\o\etaeta\d922802\old\3\sch-m32
 PLOT SCALE = 50.0000 / IN.
 USER NAME = koranjo