CONTRACT NO. 98950

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	195
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* FAI 57 & FAU 9629 (OLD IL 13)
** (X1-6-2)VB-2, (X1-6)HBK-2

TEMPORARY PAVEMENT MARKINGS - FAI 57 STAGE 2

LOCATION STATION TO STATION	PAVEMENT MARKING TAPE, TYPE I I I (SPECIAL)			TEMPORARY PAINT PAVEMENT MARKING											SHORT TERM PAVEMENT MARKING	
	LINE 4"			LINE 4"				LINE 6"	LINE 8"		LINE 12"		LINE 24"	LETTERS AND SYMBOLS		
	SKIP-DASH WHITE	SOLID WHITE	SOLID YELLOW	SKIP-DASH WHITE	SOLID WHITE	SKIP-DASH YELLOW	SOLID YELLOW	SOLID WHITE	SOLID WHITE	SOLID YELLOW	SOLID WHITE	SOLID YELLOW	SOLID WHITE		WHITE	YELLOW
	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT	FOOT	FOOT
FAI 57																
NORTHBOUND																
STA. 1506+05 TO STA. 1506+90				22			85									
STA. 1506+90 TO STA. 1510+48.26 BK				90	359		359									
STA. 1510+49.47 AH TO STA. 1512+10				41	161		161									
STA. 1512+10 TO STA. 1514+00				48			190									
STA. 1514+00 TO STA. 1518+78				120												
STA. 1515+60.11 TO STA. 1518+78 ON RAMP E				80												
STA. 1518+78 TO STA. 1527+53				219	875											
STA. 1526+85 TO STA. 1527+53 ON RAMP EE							68									
STA. 1527+53 TO STA. 1530+71				80												
STA. 1530+71 TO STA. 1538+05				184	734											
STA. 1538+05 TO STA. 1550+85				320	1,280		1280									
STA. 1550+85 TO STA. 1552+18				34	133											
SOUTHBOUND																
STA. 1499+15 TO STA. 1504+00				122	485											
STA. 1503+10 TO STA. 1504+00 ON RAMP C SEE NOTE 1					90					90						
STA. 1504+00 TO STA. 1506+34 ON RAMP C				59	234											
STA. 1504+00 TO STA. 1506+34				59												
STA. 1506+34 TO STA. 1509+43.5 BK				78	310											
STA. 1509+15.58 AH TO STA. 1517+34				205	819											
STA. 1517+34 TO STA. 1518+99				42												
STA. 1518+99 TO STA. 1526+70				193	771											
STA. 1518+99 TO STA. 1519+37 ON RAMP F							38									
STA. 1526+25 TO STA. 1526+70 ON RAMP FF SEE NOTE 1										45						
STA. 1526+70 TO STA. 1529+88 ON RAMP FF				80												
STA. 1526+70 TO STA. 1529+88				80												
STA. 1529+88 TO STA. 1535+15				132												
STA. 1535+15 TO STA. 1535+69					54		54									
STA. 1535+69 TO STA. 1536+00 SEE NOTE 2					62		31									
STA. 1536+00 TO STA. 1556+00				500	2000		2000									
STA. 1556+00 TO STA. 1556+85 SEE NOTE 2					170		85									
FAI 57 STAGE 2 PROJECT SUBTOTALS	0	0	0	2,788	8,537	0	4,351	0	0	135	0	0	0	0	0	0
FAI 57 STAGE 2 PROJECT TOTALS		0			15,676			0	135		0		0	0	0	

NOTE: 1.) THE LEFT SOLID YELLOW LINE IS 8" WIDE. THEREFORE 2 STRIPS OF 4" TAPE SHALL BE PLACED.
2.) THE CENTERLINE AND THE RT. EDGELINE ARE BOTH SOLID WHITE.

PLOT DATE = 1/16/2007
FILE NAME = c:\pw_work\pw_902602\cddi3\cddi3schm32
PLOT SCALE = 50.0000 ' / IN.
USER NAME = kwenzel

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

SCALE: VERT. HORIZ.
DATE
DRAWN BY JCK
CHECKED BY