CONTRACT NO. 98950

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	226
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* FAI 57 & FAU 9629 (OLD IL 13)
** (X1-6-2)VB-2, (X1-6)HBK-2

SEEDING - FAI 57 STAGE 3

LOCATION STATION TO STATION	TEMPORARY EROSION CONTROL SEEDING	SEEDING, CLASS 1B	SEEDING, CLASS 7	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	AGRICULTURAL GROUND LIMESTONE	MULCH, METHOD 2
	POUND	ACRE	ACRE	POUND	POUND	POUND	TON	ACRE
FAI 57								
NORTHBOUND								
LT STA 1506+90 TO STA 1513+00	89	0.89	0.89	142	107	107	1.8	1.78
LT STA 1538+90 TO STA 1550+25	154	1.54	1.54	246	185	185	3.1	3.08
SOUTHBOUND								
RT STA 1536+00 TO STA 1544+50	101		1.01	40				1.01
RT STA 1536+00 TO STA 1556+00	151	1.51	1.51	242	181	181	3.0	3.02
FAI 57 STAGE 3 PROJECT TOTALS	495	3.94	4.95	670	473	473	7.9	8.89

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

SCALE: VERT.
HORIZ.
DATE

DRAWN BY JCK
CHECKED BY

PLOT DATE = 1/17/2007
FILE NAME = c:\pwworking\d02\d0282\d0282\sheet32.dgn
PLOT SCALE = 50.0000 ' / IN.
USER NAME = krenzjc