CONTRACT NO. 98950

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	313
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* FAI 57 & FAU 9629 (OLD IL 13)
** (X1-6-2)VB-2, (X1-6)HBK-2

PIPE UNDERDRAINS - FAI 57 STAGE 4

LOCATION STATION TO STATION	PIPE UNDERDRAINS 4" FOOT	PIPE UNDERDRAINS 4" (SPECIAL) FOOT	CONCRETE HEADWALL FOR PIPE DRAINS EACH	SHOULDER REMOVAL & REPLACEMENT 8" FOOT	PIPE UNDERDRAIN REMOVAL FOOT	COMMENTS
FAI 57						
NORTHBOUND						
LT (OUTSIDE SHOULDER)						
1513+00 TO 1515+60					260	
GAP STRUCTURE #100-0086						
1517+56 TO 1523+45	589				589	
1517+56		39	1			
1522+15		43		10		REUSE HEADWALL FORM STA 1520+95
1520+95				10	24	EXISTING OUTLET
1525+86 TO 1528+80	294				294	
1526+75		58	1			OUTLET GOES AGAINST RAMP EE
GAP STRUCTURE #100-0084						
1531+14 TO 1538+90	776				776	
1535+00				10	21	EXISTING OUTLET
1535+40		43		10		REUSE HEADWALL FROM STA 1535+00
SOUTHBOUND						
RT (OUTSIDE SHOULDER)						
1510+00 TO 1511+80	180				180	
1511+80 TO 1515+58.02	378				378	
1510+05				10	15	EXISTING OUTLET
1511+00		34	1	10		REUSE HEADWALL FROM STA 1510+05
GAP STRUCTURE #100-0087						
1517+54 TO 1519+25	171				171	
1517+54		43	1			
1522+15 TO 1528+78	663				663	
1522+15		45	1	10		
1524+00				10	17	EXISTING OUTLET
1525+15		46		10		REUSE HEADWALL FROM STA 1524+00
GAP STRUCTURE #100-0085						
1531+12 TO 1536+00	488				488	
1535+25		25				
RAMP E						
RT						
12+70 TO 14+65	195				195	
14+65		18	1			
RAMP EE						
RT						
6+14 TO 8+97	283				283	
RAMP F						
RT						
2+78 TO 4+42	164				164	
2+78		18	1			
RAMP FF						
RT						
8+00 TO 9+95	195				195	
FAI 57 STAGE 4 PROJECT TOTALS	4,376	412	7	90	4,713	

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

SCALE: VERT. HORIZ.
DATE
DRAWN BY JCK
CHECKED BY

PLOT DATE = 11/2/2006
FILE NAME = c:\projects\d902802\oldl3\oldl3sch.m32
PLOT SCALE = 50.0000 ' / IN.
USER NAME = kranzjo