CONTRACT NO. 98950

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	314
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* FAI 57 & FAU 9629 (OLD IL 13)
** (X1-6-2)VB-2, (X1-6)HBK-2

EARTHWORK - FAI 57 STAGE 4

LOCATION STA TO STA	EARTH EXCAVATION	FOR INFORMATION ONLY					BORROW EXCAVATION	REMARKS
		AVERAGE SHRINKAGE FACTOR	EARTH EXCAVATION (ADJUSTED)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) SHORTAGE (-)	BORROW SWELL FACTOR		
	CU YD	%	CU YD	CU YD	CU YD	%	CU YD	
FAI 57								
STA 1510+00 TO STA 1538+90	641	15.7%	540	39,238	-38,698			
STA 1529+09 TO STA 1530+83 BRIDGE CONE	1,167	16.5%	974	605	369			
STA 1515+92 TO STA 1517+25 BRIDGE CONE	0	15.4%	0	2,941	-2,941			
FAI 57 STAGE 4 PROJECT TOTAL	**1,808**	15.9%	1,514	42,784	-41,270	25.0%	**51,588**	

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

SCALE: VERT. HORIZ.
DATE
DRAWN BY JCK
CHECKED BY

PLOT DATE = 1/16/2007
FILE NAME = c:\pw_pw1\k0020087\sdi13\sdi13sch.sht
PLOT SCALE = 50.000 ' / IN.
USER NAME = kramajo