

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	317
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

- FAI 57 & FAI 9629 (OLD IL 13)
- ** (X1-6-2)VB-2, (X1-6)HBK-2

SEEDING - FAI 57 STAGE 4

LOCATION STATION TO STATION	TEMPORARY EROSION CONTROL SEEDING	SEEDING, CLASS 1B	SEEDING, CLASS 7	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	AGRICULTURAL GROUND LIMESTONE	MULCH, METHOD 2
	POUND	ACRE	ACRE	POUND	POUND	POUND	TON	ACRE
FAI 57								
NORTHBOUND								
LT STA 1513+00 TO STA 1516+45	55	0.55	0.55	88	66	66	1.1	1.10
LT STA 1516+73 TO STA 1519+58	30	0.30	0.30	48	36	36	0.6	0.60
LT STA 1519+70 TO STA 1523+45	24		0.24	10				0.24
LT STA 1525+85 TO STA 1529+60	64	0.64	0.64	102	77	77	1.3	1.28
LT STA 1530+00 TO STA 1537+02	69	0.69	0.69	110	83	83	1.4	1.38
LT STA 1537+02 TO STA 1538+90	26		0.26	10				0.26
SOUTHBOUND								
RT STA 1510+00 TO STA 1516+40	100	1.00	1.00	160	120	120	2.0	2.00
RT STA 1516+73 TO STA 1519+25	37	0.37	0.37	59	44	44	0.7	0.74
RT STA 1522+30 TO STA 1525+60	18		0.18	7				0.18
RT STA 1526+81 TO STA 1529+46	20	0.20	0.20	32	24	24	0.4	0.40
RT STA 1530+72 TO STA 1536+00 SEE NOTE 1	77		0.77	31				0.77
FAI 57 STAGE 4 PROJECT TOTALS								
	520	3.75	5.20	657	450	450	7.5	8.95

NOTE 1: QUANTITY INCLUDES DITCH THAT IS PROPOSED IN STAGE 3

PLOT DATE = 1/17/2007
 PLOT SCALE = 1" = 500'
 USER NAME = krenzje

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCHEDULE SCALE: VERT. HORIZ. DATE
		DRAWN BY JCK CHECKED BY