

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
•	**	WILLIAMSON	917	319
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

- FAI 57 & FAU 9629 (OLD IL 13)
- ** (X1-6-2)VB-2, (X1-6)HBK-2

TEMPORARY PAVEMENT MARKINGS - FAI 57 STAGE 4

LOCATION STATION TO STATION	PAVEMENT MARKING TAPE, TYPE I I I (SPECIAL)			TEMPORARY PAINT PAVEMENT MARKING										LETTERS AND SYMBOLS SQ FT	SHORT TERM PAVEMENT MARKING	
	LINE 4"			LINE 4"				LINE 6"	LINE 8"		LINE 12"		LINE 24"		WHITE	YELLOW
	SKIP-DASH WHITE FOOT	SOLID WHITE FOOT	SOLID YELLOW FOOT	SKIP-DASH WHITE FOOT	SOLID WHITE FOOT	SKIP-DASH YELLOW FOOT	SOLID YELLOW FOOT	SOLID WHITE FOOT	SOLID WHITE FOOT	SOLID YELLOW FOOT	SOLID WHITE FOOT	SOLID YELLOW FOOT	SOLID WHITE FOOT			
FAI 57 NORTHBOUND																
STA. 1506+90 TO STA. 1510+48.26 BK				90	358		358									
STA. 1510+49.47 AH TO STA. 1523+45				320	1,296		1103									
STA. 1523+45 TO STA. 1524+26 SEE NOTE 2					603		81									
STA. 1524+26 TO STA. 1524+85				20	70		59									
STA. 1524+85 TO STA. 1525+86				30	107		101									
STA. 1525+86 TO STA. 1538+90				330	1,304		1304									
STA. 1538+90 TO STA. 1540+00 SEE NOTE 2					220		110									
STA. 1540+00 TO STA. 1550+00				250	1,000		1000									
FAI 57 SOUTHBOUND																
STA. 1501+60 TO STA. 1503+00 SEE NOTE 2					374		160									
STA. 1503+00 TO STA. 1503+17 SEE NOTE 2				10	61		22									
STA. 1503+17 TO STA. 1505+90 SEE NOTE 2				70	819		273									
STA. 1505+90 TO STA. 1509+43.5 BK				90	355		354									
STA. 1509+15.58 AH TO STA. 1510+00				20	84		84									
STA. 1510+00 TO STA. 1519+25				230	925		732									
STA. 1519+25 TO STA. 1521+55 SEE NOTE 2				60	481		230									
STA. 1521+55 TO STA. 1522+15 SEE NOTE 2					196		60									
STA. 1522+15 TO STA. 1530+27				200	812		812									
STA. 1530+27 TO STA. 1536+00 SEE NOTE 2				140	1201		595									
STA. 1536+00 TO STA. 1537+10					220		110									
STA. 1537+10 TO STA. 1545+05 I-57 AND TEMP FF				200	1590		1590									
STA. 1545+05 TO STA. 1547+30 SEE NOTE 2				60	1125		225									
STA. 1547+30 TO STA. 1548+90				80	160		160									
STA. 1548+90 TO STA. 1555+85				170	695		695									
FAI 57 STAGE 4 PROJECT SUBTOTALS	0	0	0	2,370	14,056	0	10,218	0	0	0	0	0	0	0	0	0
FAI 57 STAGE 4 PROJECT TOTALS	0				26,644			0	0	0	0	0	0	0	0	0

NOTE:1.) THE LEFT SOLID YELLOW LINE IS 8" WIDE. THEREFORE 2 STRIPS OF 4" TAPE SHALL BE PLACED.
 NOTE:2.) SEE CALCULATIONS AND/OR PLANS FOR CLARIFICATION OF QUANTITIES

PLOT DATE = 1/16/2007
 FILE NAME = c:\prow\prow\98950\old\old\prow\m32
 USER NAME = h-jay

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCHEDULE
SCALE: VERT.	DRAWN BY JCK	CHECKED BY
DATE		