

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
**	**	WILLIAMSON	917	322
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

- \* FAI 57 & FAU 9629 (OLD IL 13)
- \*\* (X1-6-2)VB-2, (X1-6)HBK-2

### GUARD RAIL - FAI 57 STAGE 4

LOCATION STATION TO STATION	CORING FOR GUARDRAIL INSTALLATION	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 1, (FLARED) EACH	STEEL PLATE BEAM GUARD RAIL, TYPE A FOOT	TRAFFIC BARRIER TERMINAL, TYPE 2 EACH	TRAFFIC BARRIER TERMINAL, TYPE 5 EACH	TRAFFIC BARRIER TERMINAL, TYPE 6 EACH	TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (FLARED) EACH	GUARDRAIL REMOVAL FOOT	TEMPORARY STEEL PLATE BEAM GUARDRAIL, TYPE A FOOT	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 5 EACH	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 6 EACH	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 10 EACH	REMARKS
	FOOT	EACH	FOOT	EACH	EACH	EACH	FOOT	FOOT	EACH	EACH	EACH		
<b>FAI 57 NORTHBOUND</b>													
<b>LT (OUTSIDE SHOULDER)</b>													
STA. 1513+00 TO STA. 1514+95								195.0	193.0				SEE NOTE 1
STA. 1514+95 TO STA. 1515+93.11			87.5		1			90.0					CONNECTS TO STRUCTURE #100-0087
STA. 1527+30 TO STA. 1529+17								188.0					EXISTING RAMP EE GUARDRAIL
STA. 1528+80 TO STA. 1529+12			12.5	1	1								CONNECTS TO STRUCTURE #100-0084
STA. 1530+84.23 TO STA. 1537+02		1					1	388.0	550.0				SEE NOTE 1 & 2 - CONNECTS TO STRUCTURE #100-0084
<b>SOUTHBOUND</b>													
<b>RT (OUTSIDE SHOULDER)</b>													
STA. 1510+00 TO STA. 1515+91.02							1	582.0	562.5				SEE NOTE 1 - CONNECTS TO STRUCTURE #100-0087
STA. 1526+20 TO STA. 1529+07								294.0					EXISTING RAMP FF GUARDRAIL
<b>RAMP E</b>													
<b>RT</b>													
STA. 12+71 TO STA. 15+02								221.0					EXISTING RAMP E GUARDRAIL
<b>RAMP F</b>													
<b>RT</b>													
STA. 2+39 TO STA. 4+40								196.0					EXISTING RAMP F GUARDRAIL
<b>RAMP FF</b>													
<b>RT</b>													
STA. 12+01 TO STA. 12+69.9			25.0	1	1			42.0					CONNECTS TO STRUCTURE #100-0087
<b>FAI 57 STAGE 4 PROJECT TOTALS</b>													
	0.0	1	125.0	2	3	2	0	2,196.0	1,305.5	0	0	0	

- NOTE: 1.) THE FACE OF THE TEMPORARY STEEL PLATE BEAM GUARDRAIL, TYPE A SHALL BE PLACED NEXT TO THE 2 FT BITUMINOUS SHOULDER WITH A 2 FT SHELF OF RIPRAP BEHIND IT. SEE TYPICAL FOR MORE CLARIFICATION.  
 2.) THE TEMPORARY TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED) SHALL USE A FLARE RATE OF 15:1.

PLOT DATE = 12/15/2006  
 FILE NAME = c:\p-c\jms\145922022\1413\1413.dwg  
 PLOT SCALE = 1/8" = 1'-0"  
 USER NAME = jms

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
SCALE: VERT. DATE		DRAWN BY JCK CHECKED BY
HORIZ.		

**SCHEDULE**