CONTRACT NO. 98950

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	366
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* FAI 57 & FAU 9629 (OLD IL 13)
** (X1-6-2)VB-2, (X1-6)HBK-2

BITUMINOUS PAVEMENT - FAI 57 STAGE 5

LOCATION STATION TO STATION	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE SUPERPAVE MIX D, N105	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE SUPERPAVE MIX E, N105	POLYMERIZED BITUMINOUS CONCRETE BINDER COURSE SUPERPAVE IL-19.0, N105	BITUMINOUS CONCRETE BINDER COURSE SUPERPAVE IL-19.0, N90 INFO. ONLY		BITUMINOUS CONCRETE PAVEMENT (FULL DEPTH) SUPERPAVE, 14 1/4" FOR INFORMATION ONLY POLY BIT SURFACE MIX D, N105 1 1/2"	POLY BIT BINDER IL-19.0, N105 2 1/4"	BIT BINDER IL-19.0, N90 10 1/2"		STABILIZED SUB-BASE 4"	STABILIZED SUB-BASE (VARIABLE DEPTH)	SUB-BASE GRANULAR MATERIAL, 6"	SUB-BASE GRANULAR MATERIAL, 10"	SUB-BASE GRANULAR MATERIAL, TYPE C	BITUMINOUS MATERIAL (PRIME COAT)	AGGREGATE (PRIME COAT)	MATERIAL TRANSFER DEVICE
	TON	TON	TON	THICKNESS (IN.)	TON	TON	TON	TON	SQ YD	SQ YD	TON	SQ YD	SQ YD	TON	GALLON	TON	TON
FAI 57																	
SOUTHBOUND																	
STA 1519+25 TO STA 1520+00				VAR	168.0							228.0					
STA 1520+00 TO STA 1520+50				VAR	111.0							138.0					
STA 1520+50 TO STA 1521+00				VAR	102.0							72.0		5			
STA 1521+00 TO STA 1521+50				VAR	110.0							29.0		5			
STA 1521+50 TO STA 1522+15				VAR	139.0							34.0		6			
RAMP F																	
STA 4+40 TO STA 7+50						46.0	85.0	324.0	551.0						176.0		
STA 7+50 TO STA 10+00						37.0	70.0	273.0	444.0						141.0		
STA 10+00 TO STA 12+62						39.0	73.0	287.0	466.0						149.0		
STA 12+62 TO STA 13+50										386.0							
STA 13+50 TO STA 14+23										357.0							
STA 14+23 TO STA 15+38.45										757.0							
RT STA 4+40 TO STA 7+64														115			
RT STA 7+64 TO STA 10+00														61			
RT STA 10+00 TO STA 12+62														67			
RT STA 12+62 TO STA 13+50														23			
RT STA 13+50 TO STA 14+23														19			
RT STA 14+23 TO STA 15+38.45														30			
LT STA 5+00 TO STA 11+21.8														111			
RAMP FF																	
STA 0+34 TO STA 1+88										608.0							
STA 1+88 TO STA 2+70										146.0							
STA 2+70 TO STA 3+38										121.0							
STA 3+37.79 TO STA 5+00						24.0	46.0	178.0	289.0						92.0		
STA 5+00 TO STA 8+00						45.0	83.0	329.0	533.0						171.0		
RT STA 0+34 TO STA 1+88														52			
RT STA 1+88 TO STA 2+70														21			
RT STA 2+70 TO STA 3+38														18			
RT STA 3+38 TO STA 4+50														29			
RT STA 4+50 TO STA 6+40														49			
RT STA 6+40 TO STA 8+00														57			
LT STA 4+55.6 TO STA 6+00														26			
LT STA 6+00 TO STA 7+85														33			
FAI 57 STAGE 5 PROJECT TOTALS	0	0	0		630				2,283	2,375	0	501	0	727	729.0	0	0

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

SCALE: VERT. HORIZ.

DATE

DRAWN BY JCK

CHECKED BY

PLOT DATE = 1/16/2007
FILE NAME = c:\pw_work\PW02082\old3\old3mchsm32
PLOT SCALE = 50.0000 / IN.
USER NAME = krenzjc