

SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
**	WILLIAMSON	917	377
STA. TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT	
* FAI 57 & FAU 9629 (OLD IL 13) ** (X1-6-2)VB-2, (X1-6)HBK-2			

EROSION CONTROL - FAI 57 STAGE 5

LOCATION STATION TO STATION	PIPE CULVERT (EROSION CONTROL)	EROSION CONTROL BLANKET	HEAVY DUTY EXCELSIOR BLANKET	PERIMETER EROSION BARRIER	EARTH EXCAVATION FOR EROSION CONTROL	AGGREGATE (EROSION CONTROL)	TEMPORARY DITCH CHECKS	INLET & PIPE PROTECTION	END SECTIONS 8"	REMARKS
	FOOT	SQ YD	SQ YD	FOOT	CU YD	TON	EACH	EACH	EACH	
FAI 57 SOUTHBOUND										
RT STA 1519+25 TO STA 1522+30		577.0								
RAMP F										
I-57 RAMP F: GORE AREA										
LT STA 5+25 TO STA 8+50		298.0					4.0			TEMP STAGE DITCH
LT STA 7+50							1.0			TEMP STAGE DITCH
LT STA 8+75							1.0			
LT STA 8+90								1.0		
LT STA 10+00							1.0			TEMP STAGE DITCH
LT STA 10+80								1.0		
LT STA 14+00								1.0		TEMP STAGE DITCH
LT STA 14+00 TO STA 15+25		1,246.5								
RT STA 2+77 TO STA 7+50		2,688.0								
RT STA 4+50 TO STA 9+50				956.0						TWO ROWS OF BARRIER
RT STA 5+00	41.0					4.0			2.0	
RT STA 7+00	38.0					4.0			2.0	
RT STA 9+00	50.0					4.0			2.0	
RT STA 9+50 TO STA 14+00				1,372.0						THREE ROWS OF BARRIER
RT STA 10+50	102.0					6.0			3.0	
RT STA 12+50	42.0					4.0			2.0	
RT STA 14+00 TO STA 15+50				311.0						TWO ROWS OF BARRIER
RT STA 14+25	10.0					2.0			1.0	
RT STA 14+25 TO STA 15+40										
RT STA 14+00 TO STA 15+25		888.5								
TEMPORARY 1:1 SLOPES										
LT STA 5+00 TO STA 8+50			147.0							
LT STA 9+00 TO STA 11+25							2.0			
RT STA 12+25 TO STA 15+50							2.0			
STAGE 5A GORE AREA										
TEMPORARY 1:1 SLOPES										
RT STA 10+00 TO STA 11+25			61.0							
LT STA 11+50 TO STA 15+25			254.0							
I-57 RAMP FF: GORE AREA										
LT STA 6+25 TO STA 7+50		190.0					4.0			
RT STA 0+43 TO STA 2+00								1.0		ONE ROW OF BARRIER
RT STA 1+67				224.0						
RT STA 2+00 TO STA 4+50										
RT STA 3+00	10.0					2.0			1.0	TWO ROWS OF BARRIER
RT STA 4+50 TO STA 8+00										
RT STA 5+00	10.0					2.0			1.0	
RT STA 6+50	32.0					4.0			2.0	
FAI 57 STAGE 5 PROJECT TOTAL	335.0	5,888.0	462.0	2,863.0	0.0	32.0	15.0	4.0	16.0	

PLOT DATE = 1/16/2007
 FILE NAME = c:\p\projects\982800\stage5\stage5.dwg
 PLOT SCALE = 80.0000 / 1 IN.
 USER NAME = krenzj

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION	
NAME	DATE	SCHEDULE	
		SCALE: VERT. / HORIZ. DATE	
		DRAWN BY JCK CHECKED BY	