

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	426
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

- * FAI 57 & FAI 9629 (OLD IL 13)
- ** (X1-6-2)VB-2, (X1-6)HBK-2

PIPE UNDERDRAINS - FAI 57 STAGE 6

LOCATION STATION TO STATION	PIPE UNDERDRAINS 4"	PIPE UNDERDRAINS 4" (SPECIAL)	CONCRETE HEADWALL FOR PIPE DRAINS	SHOULDER REMOVAL & REPLACEMENT 8"	PIPE UNDERDRAIN REMOVAL	COMMENTS
	FOOT	FOOT	EACH	FOOT	FOOT	
FAI 57						
RAMP E						
RT						
0+34 TO 6+38	538					
0+80 TO 12+69	1,192					SEE NOTE 1
		14				REUSE HEADWALL FROM EXISTING STA 5+93
		14				REUSE HEADWALL FROM EXISTING STA 9+80
						EXISTING STATION & OUTLET - SEE NOTE 1
						EXISTING STATION & OUTLET - SEE NOTE 1
		14	1			
LT						
6+38.7 TO 12+69	630					SEE NOTE 4
		12				REUSE HEADWALL FROM EXISTING STA 1+75
		12	1			
						EXISTING STATION & OUTLET - SEE NOTE 1
RAMP EE						
RT						
8+97 TO 19+30	1,033					SEE NOTE 1
						EXISTING OUTLET - SEE NOTE 1
						USE HEADWALL FROM STA 9+67
		14				REUSE HEADWALL FROM EXISTING STA 3+00
		14				REUSE HEADWALL FROM EXISTING STA 6+25
						EXISTING STATION & OUTLET - SEE NOTE 1
						EXISTING STATION & OUTLET - SEE NOTE 1
LT						
8+97 TO 14+24	527					SEE NOTE 1
						EXISTING STATION & OUTLET - SEE NOTE 1
						EXISTING STATION & OUTLET - SEE NOTE 1
		12				REUSE HEADWALL FROM EXISTING STA 10+10
FAI 57 STAGE 6 PROJECT TOTALS	3,920	120	2	0	0	

NOTE: 1.) THE EXISTING PIPE UNDERDRAIN REMOVAL IS TO BE INCLUDED WITH THE PAY ITEM PAVEMENT REMOVAL

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCHEDULE
SCALE: VERT.	DATE	DRAWN BY JCK
HORIZ.		CHECKED BY