

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	493
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

- * FAI 57 & FAU 9629 (OLD IL 13)
- ** (X1-6-2)VB-2, (X1-6)HBK-2

EARTHWORK - FAI 57 STAGE 7

LOCATION STA TO STA	EARTH EXCAVATION CU YD	FOR INFORMATION ONLY						REMARKS
		AVERAGE SHRINKAGE FACTOR %	EARTH EXCAVATION (ADJUSTED) CU YD	EMBANKMENT CU YD	EARTHWORK BALANCE WASTE (+) SHORTAGE (-) CU YD	BORROW SWELL FACTOR %	BORROW EXCAVATION CU YD	
FAI 57								
STA 1513+00 TO STA 1542+50 MEDIAN	27	25.6%	20	2,365	-2,345			
STA 1515+92 TO STA 1517+25 BRIDGE CONE	0	17.2%	0	734	-734			
STA 1529+09 TO STA 1530+83 BRIDGE CONE	1,438	36.8%	908	1	907			
FAI 57 STAGE 7 PROJECT TOTAL	1,465	26.5%	928	3,100	-2,172	25.0%	2,715	

RAISED PAVEMENT MARKERS - FAI 57 STAGE 7

LOCATION STATION TO STATION	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL EACH	RAISED REFLECTIVE PAVEMENT MARKER		
		ONE-WAY AMBER EACH	TWO-WAY AMBER EACH	ONE-WAY CRYSTAL EACH
FAI 57				
NORTHBOUND				
STA. 1505+56 TO STA. 1515+56		26		26
STA. 1517+63 TO STA. 1528+73		28		28
STA. 1531+15 TO STA. 1550+00		48		48
SOUTHBOUND				
STA. 1501+60 TO STA. 1515+53		35		35
STA. 1517+61 TO STA. 1528+70		28		28
STA. 1531+19 TO STA. 1550+00		48		48
FAI 57 STAGE 7 PROJECT SUBTOTALS			0	0
FAI 57 STAGE 7 PROJECT TOTALS		213	213	213

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

SCALE: VERT.
HORIZ.
DATE

DRAWN BY JCK
CHECKED BY