CONTRACT NO. 98950

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	494
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* FAI 57 & FAU 9629 (OLD IL 13)
** (X1-6-2)VB-2, (X1-6)HBK-2

TEMPORARY PAVEMENT MARKINGS - FAI 57 STAGE 7

LOCATION STATION TO STATION	PAVEMENT MARKING TAPE, TYPE I I I (SPECIAL)			TEMPORARY PAINT PAVEMENT MARKING											SHORT TERM PAVEMENT MARKING	
	LINE 4"			LINE 4"				LINE 6"	LINE 8"		LINE 12"		LINE 24"	LETTERS AND SYMBOLS		
	SKIP-DASH WHITE	SOLID WHITE	SOLID YELLOW	SKIP-DASH WHITE	SOLID WHITE	SKIP-DASH YELLOW	SOLID YELLOW	SOLID WHITE	SOLID WHITE	SOLID YELLOW	SOLID WHITE	SOLID YELLOW	SOLID WHITE		WHITE	YELLOW
	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT	FOOT	FOOT
FAI 57																
NORTHBOUND																
STA 1505+60 TO STA 1506+90					70		70									
STA 1506+90 TO STA 1510+48.26 BK SEE NOTE 2					716		358									
STA 1510+49.47 TO STA 1513+00					502		251									
STA 1513+00 TO STA 1525+86	30	133	133	290	1,153		1153									
STA 1525+86 TO STA 1526+70 SEE NOTE 2				20	420		84									
STA 1526+70 TO STA 1530+00	20	90	90	60	240		240									
STA 1530+00 TO STA 1542+33	20	84	84	290	1,149		1149									
STA 1542+33 TO STA 1550+00 SEE NOTE 2					1,534		767									
STA 1550+00 TO STA 1551+75				40			175									
SOUTHBOUND																
STA 1500+00 TO STA 1502+12				50	212		212									
STA 1502+12 TO STA 1507+48 SEE NOTE 2					1,845		972									
STA 1507+48 TO STA 1509+43.5 BK					392		196									
STA 1509+15.58 AH TO STA 1510+00					169		85									
STA 1510+00 TO STA 1514+80				120	480		480									
STA 1514+80 TO STA 1515+90					220		110									
STA 1515+90 TO STA 1517+25		266	133													
STA 1517+25 TO STA 1518+35					222		110									
STA 1518+35 TO STA 1519+25				20	90		90									
STA 1519+25 TO STA 1520+25				30	200		100									
STA 1520+25 TO STA 1525+85				140	560		560									
STA 1525+85 TO STA 1526+70				20	275		85									
STA 1526+70 TO STA 1527+75				30			105									
STA 1527+75 TO STA 1534+80	40	174	174	140	531		531									
STA 1534+80 TO STA 1535+90 SEE NOTE 2				30	440		110									
STA 1535+90 TO STA 1539+00				160	310		310									
STA 1539+00 TO STA 1542+33				90	335		333									
STA 1542+33 TO STA 1549+93					1520		760									
STA 1549+93 TO STA 1556+00				150	607		607									
STA 1556+00 TO STA 1556+85				20			85									
FAI 57 STAGE 7 PROJECT SUBTOTALS	110	747	614	1,700	14,192	0	10,088	0	0	0	0	0	0	0	0	0
FAI 57 STAGE 7 PROJECT TOTALS		1,471			25,980			0	0		0		0	0	0	

NOTE: 1.) THE LEFT SOLID YELLOW LINE IS 8" WIDE. THEREFORE 2 STRIPS OF 4" TAPE SHALL BE PLACED.

NOTE: 2.) SEE CALCULATIONS AND/OR PLANS FOR CLARIFICATION OF QUANTITIES

PLOT DATE = 1/18/2007
FILE NAME = s:\projects\hr9202002\old13\schem32
PLOT SCALE = 50.0000 / IN.
USER NAME = krenzje

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

SCALE: VERT. HORIZ.
DATE

DRAWN BY JCK
CHECKED BY