CONTRACT NO. 98950

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	526A
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* FAI 57 & FAU 9629 (OLD IL 13)
** (X1-6-2)VB-2, (X1-6)HBK-2

TEMPORARY PAVEMENT MARKINGS - FAI 57 STAGE 7B

LOCATION STATION TO STATION	PAVEMENT MARKING TAPE, TYPE I I I (SPECIAL) LINE 4" SKIP-DASH WHITE FOOT	LINE 4" SOLID WHITE FOOT	LINE 4" SOLID YELLOW FOOT	TEMPORARY PAINT PAVEMENT MARKING LINE 4" SKIP-DASH WHITE FOOT	LINE 4" SOLID WHITE FOOT	LINE 4" SKIP-DASH YELLOW FOOT	LINE 4" SOLID YELLOW FOOT	LINE 6" SOLID WHITE FOOT	LINE 8" SOLID WHITE FOOT	LINE 8" SOLID YELLOW FOOT	LINE 12" SOLID WHITE FOOT	LINE 12" SOLID YELLOW FOOT	LINE 24" SOLID WHITE FOOT	LETTERS AND SYMBOLS SQ FT	SHORT TERM PAVEMENT MARKING WHITE FOOT	SHORT TERM PAVEMENT MARKING YELLOW FOOT
FAI 57																
NORTHBOUND																
STA 1505+60 TO STA 1506+24				16			64									
STA 1506+24 TO STA 1506+90				17	66		66									
STA 1506+90 TO STA 1510+48.26 BK				90	358		358									
STA 1510+49.47 AH TO STA 1510+93				11	44		44									
STA 1510+93 TO STA 1513+25				58	232		232									
STA 1513+25 TO STA 1514+10				22	85		85									
STA 1514+10 TO STA 1515+63 SEE NOTE 1 FOR SKIP-DASH				78	153		153									
STA 1515+63 TO STA 1516+60 SEE NOTE 1 FOR SKIP-DASH	50	97	97													
STA 1516+60 TO STA 1517+56 SEE NOTE 2 FOR SOLID WHITE	24	288	96													
STA 1517+56 TO STA 1517+63 SEE NOTE 2 FOR SOLID WHITE	2	21	7													
STA 1517+63 TO STA 1519+07 SEE NOTE 1 FOR SOLID WHITE				36	288		144		144							
STA 1519+07 TO STA 1525+87				170	680		680									
STA 1525+87 TO STA 1526+70				21	83		83									
STA 1526+70 TO STA 1528+25 SEE NOTE 1 FOR SOLID WHITE & YELLOW				39	310		310									
STA 1528+25 TO STA 1528+80 SEE NOTE 1 FOR SOLID WHITE				14	55		55		110							
STA 1528+80 TO STA 1531+14 SEE NOTE 3 FOR SOLID WHITE	59	1,170	234													
STA 1531+14 TO STA 1531+88 SEE NOTE 1 FOR SOLID WHITE				19	74		74		148							
STA 1531+88 TO STA 1534+86				75	298		298									
STA 1534+86 TO STA 1542+00				179	714		714									
STA 1542+00 TO STA 1543+00				25	100		100									
STA 1543+00 TO STA 1550+00				175	700		700									
SOUTHBOUND																
STA 1502+12 TO STA 1503+12					100		100									
STA 1503+12 TO STA 1504+15					103				103							
STA 1504+15 TO STA 1506+34 SEE NOTE 1 FOR SOLID WHITE				55	219		219		438							
STA 1506+34 TO STA 1508+10				44	176		176		176							
STA 1508+10 TO STA 1509+43.5 BK SEE NOTE 1 FOR SKIP-DASH				68	134		134									
STA 1509+15.58 AH TO STA 1513+09 SEE NOTE 1 FOR SKIP-DASH				198	393		393									
STA 1513+09 TO STA 1515+53				61	244		244		244							
STA 1515+53 TO STA 1515+61 SEE NOTE 1 FOR SOLID WHITE				2	8		8		16							
STA 1515+61 TO STA 1517+54 SEE NOTE 3 FOR SOLID WHITE	49	965	193													
STA 1517+54 TO STA 1519+39 SEE NOTE 1 FOR SOLID WHITE				47	185		185		370							
STA 1519+39 TO STA 1528+78				235	939		939									
STA 1528+78 TO STA 1531+12	59	234	234													
STA 1531+12 TO STA 1542+33				281	1,121		1,121									
STA 1542+33 TO STA 1549+93				190	760		760									
FAI 57 STAGE 7B PROJECT SUBTOTALS	243	2,775	861	2,226	8,622	0	8,439	0	1749	0	0	0	0	0	0	0
FAI 57 STAGE 7B PROJECT TOTALS	3,879			19,287				0	1,749		0		0	0	0	

NOTE: 1.) THERE ARE TWO LINES OF THIS QUANITY. SEE PLAN SHEETS.
2.) THERE ARE THREE LINES OF THIS QUANITY. SEE PLAN SHEETS.
3.) THERE ARE FIVE LINES OF THIS QUANITY. SEE PLAN SHEETS.

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

SCALE: VERT. HORIZ.
DATE
DRAWN BY JCK
CHECKED BY

PLOT DATE = 1/16/2007
FILE NAME = c:\oa\oa\k9802002\sld3\sld3schd.dgn
PLOT SCALE = 50.0000 ' / IN.
USER NAME = krenzjp