

FAP DIST.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
857	101BR-6	WHITE	100	4
FED. ROAD DIST. NO. 7		BLINDS	FED. AID PROJECT NO.	

80% FED./20% STATE

SUMMARY OF QUANTITIES (Cont'd)			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		FAP 857 1000-2A	S.N. 097-0071 X081-2A
50104650	SLOPE WALL REMOVAL	SQ YD	449	449	
50105220	PIPE CULVERT REMOVAL	FOOT	96	96	
50200100	STRUCTURE EXCAVATION	CU YD	145		145
50300225	CONCRETE STRUCTURES	CU YD	178.4		178.4
50300255	CONCRETE SUPERSTRUCTURE	CU YD	550.2		550.2
50300260	BRIDGE DECK GROOVING	SQ YD	1353		1353
50300260	CONCRETE ENCASMENT	CU YD	11.7		11.7
50300300	PROTECTIVE COAT	SQ YD	2012	228	1784
50400735	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE BULB T-BEAMS 63"	FOOT	2417		2417
50800105	REINFORCEMENT BARS	POUND	61,960	61,960	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	147,140	147,140	
50800515	BAR SPLICERS	EACH	62		62
50901125	STEEL RAILING (TEMPORARY)	FOOT	240	240	
51201500	FURNISHING STEEL PILES HP10X57	FOOT	721		721
51202000	FURNISHING STEEL PILES HP14X102	FOOT	1339		1339
51202305	DRIVING PILES	FOOT	2060		2060
51203500	TEST PILE STEEL HP10X57	EACH	1		1
51204000	TEST PILE STEEL HP14X102	EACH	1		1
51300105	TEMPORARY BRIDGE COMPLETE	EACH	1	1	
51500100	NAME PLATES	EACH	2	1	1
54003000	CONCRETE BOX CULVERTS	CU YD	268.7	268.7	
54202335	PIPE CULVERTS, TYPE 3, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 30"	FOOT	103	103	
54215547	METAL END SECTIONS 12"	EACH	4	4	
54215565	METAL END SECTIONS 30"	EACH	2	2	
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	80.8		80.8
60100945	PIPE DRAINS 12"	FOOT	202	202	
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	130		130
60900115	TYPE B INLET BOX, STANDARD 609001	EACH	4	4	
60900515	CONCRETE THRUST BLOCKS	EACH	4	4	
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	1135	1135	
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4	
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	4	4	
63200310	GUARDRAIL REMOVAL	FOOT	300	300	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	14		14
67000600	ENGINEER'S FIELD LABORATORY	CAL MO	14		14
67100100	MOBILIZATION	L SUM	1	0.5	0.5

\* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

## SUMMARY OF QUANTITIES

SCALE: VERT. \_\_\_\_\_  
 HORIZ. \_\_\_\_\_

DATE \_\_\_\_\_ DRAWN BY \_\_\_\_\_  
 CHECKED BY \_\_\_\_\_

swartzm  
 10/17/2006  
 c:\projects\94675d\03897pa.dgn