

swartzfwm
 10/17/2006
 c:\projects\94675d\03897pa.dgn

CONTRACT NO. 98960

| FAP R/L | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|-----------------------|---------|----------|----------------------|-----------|
| 857 | 101BR-6 | WHITE | 100 | 5 |
| FED. ROAD DIST. NO. 7 | | ILLINOIS | FED. AID PROJECT NO. | |

| SUMMARY OF QUANTITIES (Cont'd) | | | 80% FED / 20% STATE | | |
|--------------------------------|---|-------|---------------------|------------------------|-----------------------|
| CODE NO | ITEM | UNIT | TOTAL QUANTITIES | CONSTRUCTION TYPE CODE | |
| | | | | FAP 857 1000-2A | S.N. 097-0071 X081-2A |
| 70100200 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701331 | EACH | 1 | 1 | |
| 70100450 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701201 | L SUM | 1 | 1 | |
| 70103800 | TRAFFIC CONTROL (SPECIAL) | L SUM | 1 | 1 | |
| 70301000 | WORK ZONE PAVEMENT MARKING REMOVAL | SQ FT | 301 | 301 | |
| 70500100 | TEMPORARY STEEL PLATE BEAM GUARD RAIL, TYPE A | FOOT | 325 | 325 | |
| 70500660 | TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 5A | EACH | 4 | 4 | |
| * 78001110 | PAINT PAVEMENT MARKING - LINE 4" | FOOT | 4950 | 4036 | 914 |
| * 78100100 | RAISED REFLECTIVE PAVEMENT MARKER | EACH | 10 | 10 | |
| * 78100105 | RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE) | EACH | 6 | | 6 |
| * 78200200 | BIDIRECTIONAL PRISMATIC BARRIER REFLECTOR | EACH | 5 | | 5 |
| * 78200410 | GUARDRAIL MARKERS, TYPE A | EACH | 11 | 11 | |
| * 78201000 | TERMINAL MARKER - DIRECT APPLIED | EACH | 4 | 4 | |
| 78300100 | PAVEMENT MARKING REMOVAL | SQ FT | 289.3 | 289.3 | |
| * A2002263 | TREE, CARYA ILLINOENSIS (PECAN), CONTAINER GROWN, 3-GALLON | EACH | 60 | 60 | |
| * A2002163 | TREE CARYA LACINIOSA (SHELLBARK HICKORY), CONTAINER GROWN, 3-GALLON | EACH | 60 | 60 | |
| * A2016820 | TREE, QUERCUS SHUMARDII (SHUMARD OAK), CONTAINER GROWN, 3-GALLON | EACH | 60 | 60 | |
| * A2C050G3 | TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), CONTAINER GROWN, 3-GALLON | EACH | 60 | 60 | |
| * A2C060G3 | TREE, QUERCUS PALUSTRIS (PIN OAK), CONTAINER GROWN, 3-GALLON | EACH | 60 | 60 | |
| X0323988 | TEMPORARY SOIL RETENTION SYSTEM | SQ FT | 285.6 | 285.6 | |
| * X2500200 | TEMPORARY SEEDING | POUND | 711 | 711 | |
| X4021000 | TEMPORARY ACCESS (PRIVATE ENTRANCE) | EACH | 1 | 1 | |
| X4024000 | TEMPORARY ACCESS (FIELD ENTRANCE) | EACH | 1 | 1 | |
| X5020501 | UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 1 | EACH | 1 | | 1 |
| X5020502 | UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 2 | EACH | 1 | | 1 |
| X5020503 | UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 3 | EACH | 1 | | 1 |
| X7050169 | TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (FLARED) | EACH | 6 | 6 | |
| Z0016600 | DETOUR ROADWAY REMOVAL | SQ YD | 4354 | 4354 | |
| Z0001900 | ASBESTOS BEARING PAD REMOVAL | EACH | 44 | | 44 |
| X0323082 | DRAINAGE SCUPPERS, 05-33 | EACH | 6 | | 6 |
| * Z0054400 | ROCK FILL | CU YD | 157 | 157 | |
| Z0065100 | SETTLEMENT PLATFORMS | EACH | 1 | 1 | |
| © Z0076600 | TRAINEES | HOUR | 500 | 500 | |

* SPECIALTY ITEMS
© Y080

| REVISIONS | |
|-----------|------|
| NAME | DATE |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. _____
 HORIZ. _____

DATE _____ DRAWN BY _____
 CHECKED BY _____

Rev.